




00263307

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOOIL & GAS
CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete

☐

Report of Remedial Work

☒

Notice of Intention to Change Plans

☐

Report of Recompleation

☐

Notice of Intention to Abandon Well

☐

Other

☐

(Check appropriate space)

LEASE NAME Mary Alice Andre WELL NO. 1FIELD Pierce WILDCAT COUNTY WeldLOCATION SE SE Section 22 Township 8N Range 66W Meridian 6th P.M.
(Quarter Quarter)641.06 feet from S Section Line and 658.08 feet from E Section Line
N or S E or W

(DETAILS OF WORK)

Subject well was Bradenhead sand-oil-squeezed as follows:

Bradenhead sand-oil-squeezed perforations 9193'-9210' and 9227'-9248' with 20,000 gallons gelled crude containing one pound of sand per gallon. Breakdown pressure, 2600 psi. Maximum injection rate, 32.3 barrels per minute. Average injection rate, 31.1 barrels per minute. Maximum injection pressure, 3175 psi. Final standing pressure, 3175 psi, which bled to zero in eight minutes and went on vacuum.

Production prior to this workover: 24 bbls. oil per day; 1.2% water.

Production after this workover upon recovery of all load oil: 179 bbls. oil per day; 1.5% water.

AJJ	
DVP	
FJK	
WKS	
HHM	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

JAN 15 1958

Company The California Company Date 1/13/58

Date

Address P. O. Box 1769, Casper, Wyo. Phone No. 2-5303

Director

By

(Signature)

Title Area Supt.