

FORM
2

Rev
05/22

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

403227303

Date Received:

12/02/2022

APPLICATION FOR PERMIT TO

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

Amend ☐

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: _____

Refill ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Prosper Farms 4-65

Well Number: 2-1-6 2AH

Name of Operator: CRESTONE PEAK RESOURCES OPERATING LLC

COGCC Operator Number: 10633

Address: 1801 CALIFORNIA STREET #2500

City: DENVER

State: CO

Zip: 80202

Contact Name: Nathan Bennett

Phone: (303)312-8166

Fax: ()

Email: nbennett@civiresources.com

FINANCIAL ASSURANCE FOR PLUGGING, ABANDONMENT, AND RECLAMATION

COGCC Financial Assurance

☒ The Operator has provided or will provide Financial Assurance to the COGCC for this Well.

Surety ID Number (if applicable): 20160104

Federal Financial Assurance

☐ In checking this box, the Operator certifies that it has provided or will provide at least this amount of Financial Assurance to the federal government for this Well. (Per Rule702.a.)

Amount of Federal Financial Assurance \$ _____

WELL LOCATION INFORMATION

Surface Location

QtrQtr: NWSW Sec: 2 Twp: 4S Rng: 65W Meridian: 6

Footage at Surface: 1490 Feet FNL/FSL 553 Feet FEL/FWL

Latitude: 39.729700 Longitude: -104.638753

GPS Data: GPS Quality Value: 1.4 Type of GPS Quality Value: PDOP

Date of Measurement: 06/11/2015

Ground Elevation: 5631

Field Name: DJ HORIZONTAL NIOBRARA

Field Number: 16950

Well Plan: is ☐ Directional ☒ Horizontal (highly deviated) ☐ Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 2 Twp: 4S Rng: 65W Footage at TPZ: 1820 FNL 330 FWL
Measured Depth of TPZ: 8398 True Vertical Depth of TPZ: 7780 FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)

Sec: 6 Twp: 4S Rng: 64W Footage at BPZ: 1880 FNL 330 FEL
Measured Depth of BPZ: 23860 True Vertical Depth of BPZ: 7780 FNL/FSL FEL/FWL

Bottom Hole Location (BHL)

Sec: 6 Twp: 4S Rng: 64W Footage at BHL: 1880 FNL 330 FEL
FNL/FSL FEL/FWL

LOCAL GOVERNMENT PERMITTING INFORMATION

County: ARAPAHOE Municipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of § 24-65.1-108 C.R.S.? No

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I)(A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? ☒ Yes ☐ No

☒ If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 10/11/2022

Comments: Approved AEUSR: Approved 10/11/22

SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Mineral Owner beneath this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Surface Owner Protection Bond (if applicable): _____ Surety ID Number (if applicable): _____

MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

- ☒ Fee
☐ State
☒ Federal
☐ Indian
☐ N/A

LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

* If this Well is within a unit, describe a lease that will be developed by the Well.

* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

T4S R65W Sec. 2: All; Sec. 14: E/2; E/2NW/4; SW/4NW/4; T4S R64W: Sec. 4: NW/4NW/4; Sec. 6: S/2; NW/4; Sec. 18: N/2; N/2SW/4

Total Acres in Described Lease: 1980 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 3750 Feet
Building Unit: 3972 Feet
Public Road: 535 Feet
Above Ground Utility: 578 Feet
Railroad: 3376 Feet
Property Line: 523 Feet

INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-1398	1920	T4S R64W Sec. 6: All; T4S R65W Sec. 1, 2: All

Federal or State Unit Name (if appl): _____ Unit Number: _____

SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 330 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 620 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: _____ Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: _____ Feet

Exception Location

☐ If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers. _____

SPACING & FORMATIONS COMMENTS

Order No. 535-1092 is amended to approve an additional seven horizontal wells, for a total of nine horizontal wells, within an approximate 1,920-acre drilling & spacing unit for the Application Lands for DSU No.1 for production from the Niobrara Formation

DRILLING PROGRAM

Proposed Total Measured Depth: 23860 Feet

TVD at Proposed Total Measured Depth 7780 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: _____ Feet ☒ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than

or equal to 100 ppm? No If yes, attach an H₂S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

Beneficial reuse or land application plan submitted? _____

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	A53B	42.09	0	100	114	100	0
SURF	13+1/2	9+5/8	J55	36	0	3300	1100	3300	0
1ST	8+1/2	5+1/2	P110	17	0	23860	3682	23860	

☐ Conductor Casing is NOT planned

POTENTIAL FLOW AND CONFINING FORMATIONS

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	Denver	0	0	665	664	0-500	Groundwater Atlas	USGS HA-646 (Robson & Romero, 1981)
Groundwater	Arapahoe	665	664	1256	1239	0-500	Groundwater Atlas	USGS HA-647 (Robson & Romero, 1981)
Groundwater	Laramie-Fox Hills	1256	1239	1986	1939	0-500	Groundwater Atlas	USGS HA-650(Robson & Romero, 1981)
Confining Layer	Pierre Shale	1986	1939	2465	2399			
Groundwater	Upper Pierre Aquifer	2465	2399	3164	3069	501-1000	Electric Log Calculation	Amoco-Westan-Fischahs 1 (05-005-06204-0000)
Confining Layer	Base of Upper Pierre Aq	3164	3069	4305	4164			
Hydrocarbon	Larimer	4305	416	4425	4279			
Confining Layer	Pierre Shale	4425	4279	5478	5289			
Hydrocarbon	Sussex	5478	5289	5593	5399			
Confining Layer	Pierre Shale	5593	5399	6240	6019			
Hydrocarbon	Shannon	6240	6019	6657	6419			
Confining Layer	Pierre Shale	6657	6419	7907	7589			
Subsurface Hazard	Sharon Springs	7907	7589	8012	7659			
Hydrocarbon	Niobrara	8012	7659	23860	7780			

OPERATOR COMMENTS AND SUBMITTAL

Comments

Distance from completed zone of this wellbore to nearest completed zone of an offset well within the same unit permitted or completed in the same formation was measured to the proposed Prosper Farms 4-65 2-6-2BH operated by Crestone Peak Resources Operating LLC in 2D.

There are no wells within 1500' of this wellbore operated by another Operator.

This application is in a Comprehensive Area Plan No CAP #: _____
Oil and Gas Development Plan Name Prosper Farms 4-65 2-1-6 OGDID #: 482697
Location ID: 443722

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Andrea Gross

Title: Permit Agent Date: 12/2/2022 Email: agross@upstreampm.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved:  Director of COGCC Date: 1/12/2023

Expiration Date: 11/15/2025

API NUMBER

05 005 07517 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>
Interim Reclamation	Operator shall comply with Notice to Operators: Interim Reclamation Procedures for Delayed Operations (dated January 5, 2017).
Construction	If conductors are preset, operator shall comply with Notice to Operators: Procedures for Preset Conductors (dated September 1, 2016).
Drilling/Completion Operations	1) Submit Form 42 electronically to COGCC 2 business days prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 2 business day spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Comply with Rule 408.j. and provide cement coverage from TD to a minimum of 500' above Niobrara. Verify coverage with a cement bond log.
Drilling/Completion Operations	Operator acknowledges the proximity of the listed non-operated wells. Operator assures that this offset list will be remediated per the Offset Well Evaluation and Hydraulic Fracturing Operator Guidance Document Operator using Option 3. Operator will submit a Form 42 ("OFFSET MITIGATION COMPLETED") stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well. 005-06204 Amoco-Westan-Fischahs 1 Amoco Production Company
Drilling/Completion Operations	Per COGCC Order 1-232, Bradenhead tests shall be performed according to the following schedule and Form 17 submitted within 10 days of each test: 1) Within 60 days of rig release, prior to stimulation. If any pressure greater than 200 psi is observed or if there is continuous flow, Operator must contact COGCC engineering for approval prior to stimulation. 2) If a delayed completion, a second test is required between 6-9 months after rig release and must be conducted prior to stimulation. If any pressure greater than 200 psi is observed or if there is continuous flow, Operator must contact COGCC engineering for approval prior to stimulation. 3) A post-production test within 60 days after first sales, as reported on the Form 10, Certificate of Clearance.
5 COAs	

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	Alternative Logging Program: One of the first wells drilled on the pad will be logged with Open Hole Resistivity Log and Gamma Ray Log from the kick-off point to into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "Alternative Logging Program - No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run."
2	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling

Total: 2 comment(s)

Attachment List

<u>Att Doc Num</u>	<u>Name</u>
403227303	FORM 2 SUBMITTED
403227327	DEVIATED DRILLING PLAN
403227328	OTHER
403227329	DIRECTIONAL DATA
403231936	OffsetWellEvaluations Data
403243148	WELL LOCATION PLAT
403288047	OFFSET WELL EVALUATION

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	With operators concurrence checked Fed Minerals. Final Review Completed.	01/09/2023
Permit	Requesting to check Fed Minerals.	01/06/2023
OGLA	The Commission approved OGDG #482697 on November 16, 2022 for the Oil and Gas Location related to this Form 2. OGLA task passed.	12/05/2022

Total: 3 comment(s)