



Treatment Report

Customer: Civitas Resources

Job #: JOB00133201

Rep: Kenny
Graham

Rig: Cartel 11

Job Date: Sep 01 @ 09:09

Supervisor: James Ragle

Well: State Antelope V-B-3HN

Time Requested:

Job Type: US Primary

UWI: State Antelope V-B-3HN

Time Arrived: Sep 01 @ 09:09

Casing-
Surface

Surface: State Antelope V-B-3HN

Time Released: Sep 01 @ 15:09

1 Grade	TBD	1 Size (mm, in)	16	1 Weight (kg/m, 36 lb/ft)
2 Size (mm, in)	9.625	2 Weight (kg/m, 36 lb/ft)		BHCT (°C, °F) 89
BHST (°C, °F)	109	Collapse Csg Pressure (MPa, psi)	2020	Float Depth (m, 1609 ft)
Funnel Vis (sec/L, sec/qt)	TBD	Hole Size (mm, in)	13.5	Max Csg Pressure (MPa, psi)
Max Pressure (MPa, psi)	1500	Mud Density (kg/m3, lb/gal)	8.5	Mud Type WBM
Plug Size (mm, in)	9.625	Plug Type	Rig Supplied	TMD (m, ft) 1648
TVD (m, ft)	1593			

Treatment Info:	Tonnes Used:	Tonnes Not Used:	0.00
Preflush:	10m3 MAG Mark & 10m3 Fresh Water	Slurry Temp:	86
		Water Temp:	74
		Bulk Temp:	75
Displace:	124m3 Fresh Water		
Slurry Returns:	18 Plug Bumped: Yes	Pump Out Lines:	Float Held: Yes

Time	Pressure MPa	Annular Pressure MPa	Volume Per Stage m3	Total Stage Volume m3	Rate m3/min	Treatment Detail
15:03	1100.00					Bump Plug
09:00	0.00					Arrive on Location - REQUESTED 10:00AM GOT NUMBERS FROM COMPANY MAN RIG DRILLING
13:44	0.00					Safety Meeting - HOLD SAFETY MEETING WITH RIG CREW AND COMPANY MAN
13:55	150.00			5.00	3.5	Fill Lines - FILL LINES WITH FRESH WATER AND DROP BOTTOM PLUG
13:57	2500.00			0.50		Start Pressure Test - TEST PUMPS AND LINES
13:59	0.00					End Pressure Test
14:00	120.00			10.00	4	Pump Preflush - PUMP 10 BBLS MAG MARK
14:04	150.00			10.00	4	Pump Preflush - 10 BBLS FRESH WATER
14:07	450.00			169.00	7	Pump Slurry - MAG S 13.3PPG, 659SKS, 1.44 YIELD, 7.0 MIX WATER , 85#/SK 169BBLS

14:33	0.00					Stop Pumping
14:34	0.00					Drop Plug - DROP TOP PLUG WITNESSED BY COMPANY MAN
14:38	550.00			124.00	8	Displace - DISPLACE WITH FRESH WATER 124BBLS / 18 BBLS CEMENT BACK
14:57	600.00				4	Decrease Rate - SLOW TO LAND @ 110BBLS AWAY
15:04	0.00					Check Floats - FLOATS HELS .5BBLS BACK
15:14	0.00					Wash Up Truck
15:30	0.00					Leave Location



Customer: BONANZA CREEK

Date: 09-01-2022

Ticket: 133201

Location: 0

Well Name: STATE ANTELOPE V-B-3HN

Job Type: SURFACE

Magnum Unit #: 1507

