



Treatment Report

Customer: Civitas Resources

Job #: JOB00133468

Rep: Kenny
Graham

Rig: Cartel 11

Job Date: Sep 01 @ 20:09

Supervisor: James Ragle

Well: State Antelope 42-12-3HN

Time Requested:

Job Type: US Primary

UWI: State Antelope 42-12-3HN

Time Arrived: Sep 02 @ 01:09

Casing-
Surface

Surface: State Antelope 42-12-3HN

Time Released: Sep 02 @ 05:09

1 Grade	TBD	1 Size (mm, in)	9.625	1 Weight (kg/m, lb/ft)	36
2 Size (mm, in)	9.625	2 Weight (kg/m, lb/ft)	36	BHCT (°C, °F)	89
BHST (°C, °F)	109	Collapse Csg Pressure (MPa, psi)	2020	Float Depth (m, ft)	1604
Funnel Vis (sec/L, sec/qt)	TBD	Hole Size (mm, in)	13.5	Max Csg Pressure (MPa, psi)	3520
Max Pressure (MPa, psi)	1500	Mud Density (kg/m3, lb/gal)	8.5	Mud Type	WBM
Plug Size (mm, in)	9.625	Plug Type	Rig Supplied	TMD (m, ft)	1644
TVD (m, ft)	1593				

Treatment Info:	Tonnes Used:	Tonnes Not Used:	0.00		
Preflush:	10m3 MAG Mark & 10m3 Fresh Water			Circulation Time:	1
		Slurry Temp:	88	Bulk Sample:	Yes
Displace:	123.9m3 Fresh Water	Water Temp:	77	Water Sample:	Yes
		Bulk Temp:	75	Slurry Sample:	Yes
Slurry Returns:	30 Plug Bumped:	Yes	Pump Out Lines:	Float Held:	Yes

Time	Pressure MPa	Annular Pressure MPa	Volume Per Stage m3	Total Stage Volume m3	Rate m3/min	Treatment Detail
01:00	0.00					Arrive on Location - REQUESTED 1:00 AM GOT NUMBERS FROM COMPANY MAN RIG DRILLING
03:35	0.00					Safety Meeting - HOLD SAFETY MEETING WITH RIG CREW AND COMPANY MAN
03:41	150.00			5.00	3.5	Fill Lines - FILL LINES WITH FRESH WATER AND DROP BOTTOM PLUG
03:45	2500.00			0.50		Start Pressure Test - TEST PUMPS AND LINES
03:47	0.00					End Pressure Test
03:48	120.00			10.00	4	Pump Preflush - PUMP 10 BBLS MAG MARK
03:50	150.00			10.00	4	Pump Preflush - 10 BBLS FRESH WATER
03:53	450.00			169.00	7	Pump Slurry - MAG S 13.3PPG, 659SKS, 1.44 YIELD, 7.0 MIX WATER , 85#/SK 169BBLS
04:22	0.00					Stop Pumping

04:23	0.00					Drop Plug - DROP TOP PLUG WITNESSED BY COMPANY MAN
04:25	550.00			124.00	8	Displace - DISPLACE WITH FRESH WATER 123.9BBLS / 30 BBLS CEMENT BACK
04:48	600.00				4	Decrease Rate - SLOW TO LAND @ 114BBLS AWAY
04:50	1140.00					Bump Plug
04:51	0.00					Check Floats - FLOATS HELS .5BBLS BACK
05:02	0.00					Wash Up Truck
05:30	0.00					Leave Location



Customer: BONANZA CREEK

Date: 9-2-2022

Ticket: 133468

Location: 1

Well Name: STATE ANTELOPE 42-12-3HN

Job Type: SURFACE

Magnum Unit #: 1507

