

FORM
5Rev
12/20

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

403286530

Date Received:

DRILLING COMPLETION REPORT

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 8960

Contact Name: Kamrin Stiver

Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY

Phone: (303) 3128532

Address: 410 17TH STREET SUITE #1400

Fax:

City: DENVER

State: CO

Zip: 80202

Email: kstiver@civiresources.com

API Number 05-123-51722-00

County: WELD

Well Name: State Antelope

Well Number: C13-W43-2HN

Location: QtrQtr: SWNW Section: 2 Township: 5N Range: 62W Meridian: 6
FNL/FSL FEL/FWL

Footage at surface: Distance: 1788 feet Direction: FNL Distance: 333 feet Direction: FWL

As Drilled Latitude: 40.431850 As Drilled Longitude: -104.298840

GPS Data: GPS Quality Value: 1.1 Type of GPS Quality Value: PDOP Date of Measurement: 10/05/2022

** If directional footage at Top of Prod. Zone Dist: 1937 feet Direction: FSL Dist: 200 feet Direction: FWL
Sec: 2 Twp: 5N Rng: 62W** If directional footage at Bottom Hole Dist: 1849 feet Direction: FSL Dist: 330 feet Direction: FEL
Sec: 2 Twp: 5N Rng: 62W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number: OG-108513

Spud Date: (when the 1st bit hit the dirt) 09/04/2022 Date TD: 10/30/2022 Date Casing Set or D&A: 10/30/2022

Rig Release Date: 11/16/2022 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 11701 TVD** 6238 Plug Back Total Depth MD 11692 TVD** 6238

Elevations GR 4646 KB 4671

Digital Copies of ALL Logs must be Attached



List All Logs Run:

CBL, MWD, (RES 123-51731)

FLUID VOLUMES USED IN DRILLING OPERATIONS

(Enter "0" if a type of a fluid was not used. Do not leave blank.)

Total Fluids (bbls): 3495

Fresh Water (bbls): 707

Recycled or Reused Fluids That Offset the Use of Fresh Water (bbls): 2398

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top	Status
CONDUCTOR	26	16	A53B	52	0	124	100	124	0	VISU
SURF	13+1/2	9+5/8	J55	36	0	1655	659	1655	0	VISU
1ST	8+1/2	5+1/2	P110	20	0	11692	1880	11692	0	CBL

Bradenhead Pressure Action Threshold 496 psig

This threshold is calculated per Rule 308A.b.(2)G. If this well is located in a bradenhead test area (see Rule 207.b) per an Order of the Commission, it may be subject to a different threshold.

Does the casing centralization comply with Rule 317.g? Yes

If "NO", provide details below.

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,513		NO	NO	
SUSSEX	4,282		NO	NO	
SHANNON	4,735		NO	NO	
SHARON SPRINGS	6,326		NO	NO	
NIOBRARA	6,455		NO	NO	

Operator Comments:

The TPZ footages are estimates calculated through Directional Plotting Software—from where the production string (5 1/2" casing) crosses the 460' setback hardline. The actual footages will be submitted with the Form 5A.
Alternative Logging Program- No open hole resistivity log with gamma ray was run on this well per rule 317.p. A Resistivity log was run on State Antelope 43-13-3HN (123-51731)

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Kamrin Stiver

Title: Drilling Technician

Date: _____

Email: kstiver@civiresources.com

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
403290245	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
403290248	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
403290239	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
403290241	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
403290243	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
403290244	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)