




00544944

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOOIL & GAS
CONSERVATION COMMISSION

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Tennessee Gas Transmission Company Field - Wildcat X
Lease Name USA-S. Marvin James "A" Well No. 1 County Routt
Location NW/4 SE/4 Section 26 Township 6 N Range 86 W Meridian 6th P.M.
(Quarter Quarter)
2009 feet from S Section line and 2013 feet from E Section Line
N or S E or W

TOTAL DEPTH 5590DATE OF PLUGGING 11-13-59

DETAILS OF WORK

Plugged and abandoned by Crumpler Drilling Company. Ran drill pipe open ended and spotted cement plugs as follows: PB 5360'-16' w/ 10 sacks, PB 5220'-5176' w/ 10 sacks, PB 3700'-3659' w/ 10 sacks. Laid down DP. Ran magna-tector and jet cutter. Found free point at 2700'. Cut 7-5/8" casing at 2696'. Pulled 7-5/8" casing. Set plug #4 from 159'-129' in bottom of surface casing. Set plug #5 from 8'-2' in top of surface casing. All intervening intervals between plugs filled w/ 9.2# rotary mud.

Casing remaining in hole.

30' - 18" conductor pipe
159' - 13-3/8" 48# H40 ST&C surface casing
1022' - 7-5/8" 26.4# J55 LT&C intermediate casing

Location cleaned up and all surface equipment removed.

✓ Plugging completed 11-13-59. Final Report.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	✓
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

DEC 21 1959

Company Tennessee Gas Trans. Co. Date 12-11-59

Date

Address Box 1772, Casper, Wyoming Phone No. 2-6981

Director

By

L. C. Bodemann, Jr.
(Signature)Title Dist. Prod. Supt.

L. C. Bodemann, Jr.