

OIL & GAS
CONSERVATION COMMISSIONOIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐Report of Remedial Work ☐Notice of Intention to Change Plans ☐Report of Recompletion ☐Notice of Intention to Abandon Well ☐Other Progress report on ☒(Check appropriate space) attempt to complete for oil
Tow Creek zone 6299-6675'.LEASE NAME FederalWELL NO. 1FIELD Buck Peak

WILDCAT

COUNTY MoffatLOCATION NW SE SESection 23Township 6NRange 90WMeridian 6th P.M.1023feet from South

N or S

Section Line and

1005feet from East

E or W

Section Line

(DETAILS OF WORK)

On August 2, 1957 388' of 5½" O.D., 17#/ft., J-55, Hydril flush joint, Emsco More area (5 rows of horizontal 2" x 80 gauge slots, ¾ of an inch apart vertically.) Slotted liner casing was hung in this well. Bottom of the liner is at 6,663' and top of Burns Plain Liner hanger is at 6,275'. (7" casing shoe is at 6,299'). Above work done with drilling mud in the hole.

August 3, 1957 Displaced with crude oil from off the lease.

August 4, 1957 Flushed well with crude oil from off the lease with 7% control flow.

August 5, 1957: Swabbed hole to bottom.

August 6, 1957 Accomplished a sand oil squeeze (sand frac) job with 10,000 gal. crude oil from off the lease with 1.85#/gal. sand through open casing.

August 7, 1957 Swabbed well.

August 13, 1957 Set pumping unit and started pumping.

August 14 through 30, 1957 Pumping small volume of load oil.

AJJ	
DVR	
FJK	
WRS	
HHA	
AH	
JJD	
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Company Malco Refineries, Inc. Date 10-17-57

OCT 21 1957

Date

Address Box 660, Roswell, N.M. Phone No. MAin 2-3140

Director

By J. R. McMinn Title Prod. Supt.

(Signature) J. R. McMinn

K

18