

**OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO**



00213262

## SONDRY NOTICES AND REPORTS ON WELLS

CONSERVATION COMMISSION

## INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME Federal WELL NO. 1  
FIELD Buck Peak WILDCAT COUNTY Moffat  
LOCATION NW SE SE Section 23 Township 6N Range 90W Meridian 6th P.M.  
(Quarter Quarter)  
1023 feet from North Section Line and 1005 feet from West Section Line  
N or S E or W

(DETAILS OF WORK)

Pumped frac oil back from zone behind 5½" slotted liner below 7" shoe at 6299'. Total depth 6675', total depth inside 5½" slotted liner is 6663'.

December 13, 1957: Cleaned 63' frac sand out of liner by reverse circulation. Placed Halliburton rubber umbrella at 6273' (above 5½" liner hanger). Dumped 3 sacks Calseal in 2 runs 6266' to 6273'. Tested casing to 2500 psig. Held O.K. Perforated 7" casing 6255-6265' with 28 jets and 32 bullets 6210-6255' with 2 jets and 2 bullets per foot. Pumped in 32 gallons control flow in 26 barrels crude oil followed by 200 barrels crude oil. Now swabbing back load oil.

AJJ	
DVR	
FJK	
WRE	✓
HHM	
AH	
JJD	
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Company Malco Refineries, Inc. Date December 20, 195

Date \_\_\_\_\_

Address Box 687, Craig, Colorado Phone No. TA4-5716

Director

By H. T. Dean Title Dist. Prod. Supt  
(Signature) H. T. Dean