



262

COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS

(Indicate nature of data by checking below)

Notice of intention to drill X
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report _____

Following is a (notice of intention to do work) March 31 19 52
 (report of work done) (On land) (patented) described as follows:

Colorado	Logan	Wild Cat
State	County	Field

1	North Sterling Irrigation Co.	NE $\frac{1}{4}$	10	9 North	53 West	(Meridian)
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.)		(Twp.)	(Range)	

The well is located 330 ft. (N) of _____ and 330 ft. (E) of _____
 the South and west lines ~~(S)~~ ~~(W)~~

The elevation above sea level is 4,111. ft.

Details of Plan of Work: (State names of and expected depths to objective sands:
 Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
 ing points, and all other important proposed work.)

To test the "J" Sand of the Dakota Series expected at 5400 feet, with Rotary Tools.
 Cement 250' of 10-3/4" 32# surface casing to top of ground. If shows justify production
 test 5 1/2" 15 1/2# casing will be run through sand and cemented with approximately 200
 sacks of cement. The mud will be of such weight and viscosity that there will be no
 communication of fluids from the various sands penetrated.

Approved: APR 5 1952

 Director

Company DAVON OIL CORPORATION
 Address Box 1586, Oklahoma City, Okla.
 By
 Title President

Submit reports of proposed work, for approval, on this form in Duplicate for patented
 lands and in Triplicate for school and state lands.