


OIL AND GAS CONSERVATION COMMISSION  
COLORADO

00544917

## PLUGGING RECORD

OIL & GAS  
CONSERVATION COMMISSION

## INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Tennessee Gas Transmission Company Field Curtis Wildcat -  
 Lease Name Rocky Mountain Fuel Company Well No. 1 County Routt  
 Location N/2 NE/4 SW/4 Section 24 Township 6N Range 86W Meridian 6th PM  
 (Quarter Quarter)  
2449 feet from S Section line and 1998 feet from W Section Line  
 N or S E or W

TOTAL DEPTH 4425'DATE OF PLUGGING 10/16/59*Verbal 8/27/59*

## DETAILS OF WORK

MIRUPU - 9/17/59. Placed plug #1 - 10 sx. cement from 3700-3650'. Shot off and pulled 7" casing from 2882'. 7" casing left in well - 923', 2832-3755'. Placed plug #2 - 25 sx. cement from 325-265' at bottom of surface casing. Plug #3 - 55sx. cement at top of surface casing. All plugging done w/water in hole as well was drilled in with cable tools and open hole plugged. Erected regulation dry hole marker. P & A complete 10/16/59.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

DEC 30 1959

Date

Director

Company Tennessee Gas Trans. Co. Date 12-23-59Address P.O. Box 1772, Casper, Wyo. Phone No. 2-6981By L. C. Bodemann, Jr. District Prod.  
L. C. Bodemann (Signature) Title Superintendent