

**STATE OF COLORADO**  
**OIL AND GAS CONSERVATION COMMISSION**  
**DEPARTMENT OF NATURAL RESOURCES**  
**SUBMIT ORIGINAL AND 1 COPY**



00265372

FOR OFFICE USE			
ET	FE	UC	SE

**SUNDRY NOTICES AND REPORTS ON WELLS**

(Do not use this form for proposals to drill or to deepen of plug back to a different reservoir.  
 Use "APPLICATION FOR PERMIT-" for such proposals.)

1. <input type="checkbox"/> OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> COALBED METHANE <input type="checkbox"/> INJECTION WELL <input type="checkbox"/> OTHER			5. FEDERAL/INDIAN OR STATE LEASE NO.
2. NAME OF OPERATOR <b>TOM BROWN, INC.</b>			6. PERMIT NO.
3. ADDRESS OF OPERATOR <b>141 UNION BLVD., SUITE 400</b>			7. API NO. <b>05-057-5093</b>
CITY <b>LAKEWOOD</b> STATE <b>CO</b> ZIP CODE <b>80228</b>			8. WELL NAME <b>BLEVINS</b>
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 14 below.)  At surface <b>200' FNL &amp; 1,170' FEL Sec 10 - T9N - R78W</b>  At proposed production zone <b>As above</b>			9. WELL NUMBER <b>A-3</b>
			10. FIELD OR WILDCAT <b>Canadian River</b>
12. COUNTY <b>Jackson</b>			11. QTR. QTR. SEC., T.R. AND MERIDIAN <b>NW NE NE Sec 10 - T9N - R78W</b>

**Check Appropriate Box To Indicate Nature of Notice, Report or Notification****13A. NOTICE OF INTENTION TO:**

- ☒ PLUG AND ABANDON
- ☐ MULTIPLE COMPLETION
- ☐ COMMINGLE ZONES
- ☐ FRACTURE TREAT
- ☐ REPAIR WELL
- ☐ OTHER:

**13B. SUBSEQUENT REPORT OF:**

- ☐ FINAL PLUG AND ABANDONMENT  
SUBMIT 3RD PARTY CEMENT VERIFICATION AND JOB LOG)
- ☐ ABANDONED LOCATION (WELL NEVER DRILLED - SITE MUST BE RESTORED WITHIN 6 MONTHS)
- ☐ REPAIRED WELL
- ☐ OTHER:  
\*Use Form 5 - Well Completion or Recompletion Report and Log for subsequent report of Multiple/Commingle Completions and Recompletions

**13C. NOTIFICATION OF:**

- ☐ SHUT-IN/TEMPORARILY ABANDONED  
DATE:  
(REQUIRED EVERY 6 MONTHS)
- ☐ PRODUCTION RESUMED  
DATE:
- ☐ LOCATION CHANGE (SUBMIT NEW PLAT)
- ☐ WELL NAME CHANGE
- ☐ OTHER:

14. DESCRIBE PROPOSED OR COMPLETED OPERATIONS ON THIS FORM (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent)

**15. DATE OF WORK**

Proposal Notify Oil & Gas Conservation Commission minimum of 48 hours prior to work.  
 Existing perfs at 2038-68' now below BP @ 2030' w/ 1 sxs cement.  
 PROPOSED NEW WORK TO ABANDON WELL  
 Set bridge plug at approximately 1,919'. (50' above top perforation. Open perfs 1969-79' & 1994-2004'). Dump 2 sxs cement on plug.  
 Perf squeeze holes at 360'. (50' below surface casing shoe)  
 Break circulation up 5-1/2" - 8-5/8" annulus and pump/squeeze balanced plug of 50 sxs Class "G" cement into perfs at 360'.  
 Pump 50' (6 sxs) Class "G" cement plug from 50' to surface.  
 Run 1" tubing down 5-1/2" - 8-5/8" annulus and pump 50' (8 sxs) Class "G" cement plug from 50' to surface.  
 Cut off wellhead and casing 30" below ground level and weld steel cap on 5-1/2" casing. Reclaim location.  
 Request approval to commence work in early August after hay has been harvested from fields. Surface owner has also requested this commencement date.

16. I hereby certify that the foregoing is true and correct

SIGNED

PHONE NO. 303/980-9340

NAME (PRINT) Paul R. Brandt

TITLE Consultant

DATE 05/23/96

(This space for Federal or State office use)

APPROVED

TITLE

DATE

5/24/96

CONDITIONS OF APPROVAL, IF ANY: