



DATE: 4/25/96

057-5087

WELL NAME: BLEVINS A-8

LOCATION: NE NE 10 9N 78W

SURFACE CASING: 8 5/8 TO 309

PRODUCTION CASING: _____

PBTD: 1955' CIBP WITH 1 SK CMT

PERFORATIONS: 1920 - 27 DAKOTA

COMMENTS: PERF 1965 - 85 SQ 20 SKS 2015 - 20 CMT RET 2004
SQ 50 SKS

PLUGGING PROCEDURE: _____

① CIBP AT 1870' + DUMP 2 SKS

② PERF 360' + BALANCE 50 SKS CMT IN + OUT OF
5 1/2

③ 10 SKS TOP 5 1/2, 5 1/2 - 8 5/8 ANNULUS

④ CUT 4' BELOW GL, WECS RATE

OR CUT + PULL 5 1/2, 40 SKS 360' UP

Rn 4 INTENT TO FOLLOW