

STATE OF COLORADO
OIL AND GAS CONSERVATION COMMISSION
DEPARTMENT OF NATURAL RESOURCES
SUBMIT ORIGINAL AND 1 COPY



00265396

FOR OFFICE USE

| | | | |
|----|----|----|----|
| ET | FE | UC | SE |
|----|----|----|----|

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen of plug back to a different reservoir.
 Use "APPLICATION FOR PERMIT-" for such proposals.)

1. ☐ OIL WELL ☒ GAS WELL ☐ COALBED METHANE ☐ INJECTION WELL ☐ OTHER

5. FEDERAL/INDIAN OR STATE LEASE NO.

6. PERMIT NO.

2. NAME OF OPERATOR

TOM BROWN, INC.

3. ADDRESS OF OPERATOR

141 UNION BLVD., SUITE 400

CITY

LAKEWOOD

STATE

CO

ZIP CODE

80228

4. LOCATION OF WELL (Report location clearly and in accordance with any State

requirements. See also space 14 below.)

At surface

850' FNL & 410' FEL Sec 10 - T9N - R78W

At proposed production zone

As above

7. API NO.

05-057-5087

8. WELL NAME

BLEVINS

9. WELL NUMBER

A-8

10. FIELD OR WILDCAT

Canadian River

11. QTR. QTR. SEC., T.R. AND MERIDIAN

SE NE NE Sec 10 - T9N - R78W

12. COUNTY

Jackson**Check Appropriate Box To Indicate Nature of Notice, Report or Notification**

13A. NOTICE OF INTENTION TO:

- ☒ PLUG AND ABANDON
- ☐ MULTIPLE COMPLETION
- ☐ COMMINGLE ZONES
- ☐ FRACTURE TREAT
- ☐ REPAIR WELL
- ☐ OTHER:

13B. SUBSEQUENT REPORT OF:

- ☐ FINAL PLUG AND ABANDONMENT
SUBMIT 3RD PARTY CEMENT VERIFICATION
AND JOB LOG
- ☐ ABANDONED LOCATION (WELL NEVER DRILLED -
SITE MUST BE RESTORED WITHIN 6 MONTHS)
- ☐ REPAIRED WELL
- ☐ OTHER:
*Use Form 5 - Well Completion or Recompletion Report and Log
for subsequent report of Multiple/Commingle Completions and
Recompletions

13C. NOTIFICATION OF:

- ☐ SHUT-IN/TEMPORARILY ABANDONED
DATE:
(REQUIRED EVERY 6 MONTHS)
- ☐ PRODUCTION RESUMED
DATE:
- ☐ LOCATION CHANGE (SUBMIT NEW PLAT)
- ☐ WELL NAME CHANGE
- ☐ OTHER:

14. DESCRIBE PROPOSED OR COMPLETED OPERATIONS ON THIS FORM (Clearly state all pertinent details, and give pertinent dates,
 including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical
 depths for all markers and zones pertinent

15. DATE OF WORK

Proposal

Notify Oil & Gas Conservation Commission minimum of 48 hours prior to work.

Existing perms 2015-20' were squeezed w/ 20 sxs cement, cement retainer at 2004'.

Existing perms 2965-85' were squeezed w/ 20 sxs cement. Bridge plug set at 1955' w/ 1 sxs cement. PBTD 1937'.

PROPOSED NEW WORK TO ABANDON WELL

Set bridge plug at approximately 1,870'. (50' above top perforation. Open perms 1920-27'). Dump 2 sxs cement on plug.

Perf squeeze holes at 359'. (50' below surface casing shoe)

Break circulation up 5-1/2" - 8-5/8" annulus and pump/squeeze balanced plug of 50 sxs Class "G" cement into perms at 359'.

Pump 50' (6 sxs) Class "G" cement plug from 50' to surface.

Run 1" tubing down 5-1/2" - 8-5/8" annulus and pump 50' (8 sxs) Class "G" cement plug from 50' to surface.

Cut off wellhead and casing 26" below ground level and weld plate on 5-1/2" casing and reclaim location.

Request approval to commence work in early August after hay has been harvested from fields. Surface owner has also requested this commencement date.

16. I hereby certify that the foregoing is true and correct

SIGNED

Paul R Brandt

PHONE NO. 303/980-9340

NAME (PRINT) Paul R. Brandt

TITLE Consultant

DATE 05/23/96

(This space for Federal or State office use)

APPROVED

TITLE

DATE

5/24/96

CONDITIONS OF APPROVAL, IF ANY: