



OGCC FORM 4  
Rev. 8/89

STATE OF COLORADO  
OIL AND GAS CONSERVATION COMMISSION  
DEPARTMENT OF NATURAL RESOURCES

SUBMIT ORIGINAL AND 1 COPY



FOR OFFICE USE ONLY			
ET	FE	UC	SE

**SUNDRY NOTICES AND REPORTS ON WELLS**

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)

<input checked="" type="checkbox"/> OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> COALBED METHANE <input type="checkbox"/> INJECTION WELL <input type="checkbox"/> OTHER		5 FEDERAL INDIAN OR STATE LEASE NO
2 NAME OF OPERATOR Western Operating Company		6 PERMIT NO 71-266
3 ADDRESS OF OPERATOR 518 - 17th Street, Suite 1680		7 API NO 05-061-6105
CITY                      STATE                      ZIP CODE Denver                      CO                      80202		8 WELL NAME King Pyles
4 LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 1980' FSL & 660' FEL of Section 8		9 WELL NUMBER No. 3
At proposed prod zone Same		10 FIELD OR WILDCAT Brandon
12 COUNTY Kiowa		11 QTR QTR SEC. T.R. AND MERIDIAN NESE Section 8 T19S-R45W

Check Appropriate Box To Indicate Nature of Notice, Report or Notification

13A. NOTICE OF INTENTION TO: <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> MULTIPLE COMPLETION <input type="checkbox"/> COMMINGLE ZONES <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> REPAIR WELL <input type="checkbox"/> OTHER _____	13B. SUBSEQUENT REPORT OF: <input type="checkbox"/> FINAL PLUG AND ABANDONMENT (SUBMIT 3RD PARTY CEMENT VERIFICATION AND JOB LOG) <input type="checkbox"/> ABANDONED LOCATION (WELL NEVER DRILLED - SITE MUST BE RESTORED WITHIN 6 MONTHS) <input type="checkbox"/> REPAIRED WELL <input type="checkbox"/> OTHER _____ <small>*Use Form 3 - Well Completion or Recompletion Report and Log for subsequent reports of Multiple/Commingled Completions and Recompletions</small>	13C. NOTIFICATION OF: <input type="checkbox"/> SHUT-IN TEMPORARILY ABANDONED (DATE _____) (REQUIRED EVERY 6 MONTHS) <input type="checkbox"/> PRODUCTION RESUMED (DATE _____) <input type="checkbox"/> LOCATION CHANGE (SUBMIT NEW PLAT) <input type="checkbox"/> WELL NAME CHANGE <input type="checkbox"/> OTHER _____
---	---	---

14 DESCRIBE PROPOSED OR COMPLETED OPERATIONS ON THIS FORM (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent)

15 DATE OF WORK Third (3rd) Quarter, 1996

- TIH w/2-7/8" tbg. Tag sand plug to check depth. Spot 10 sx cement plug @ 4570'± or tag w/wireline & dump bail 10 sx plug.
- Spot 40 sx plug @ 3080'. Let cement set up. Fill csg w/water.
- Perf csg w/4 holes @ 1300'. Set cement retainer @ 1250'. Squeeze 113 sx cement through holes @ 1300'. Spot 2 sx on top of retainer.
- Perf 4 holes @ ~~190'~~<sup>210'</sup>. Squeeze 25 sx through holes @ ~~190'~~<sup>210'</sup> & leave 25 sx plug in csg. (50 sx total).
- Set 10 sx plug @ surface. Put 5 sx in 8-5/8" & 5 sx in 5-1/2". Cut off 8-5/8" & 5-1/2" 4'+below ground level. Cap w/1/4" or thicker plate that reads - King Pyles #3 NESE Sec. 8 T19S-R45W
- Reclaim location.

16. I hereby certify that the foregoing is true and correct

SIGNED *Steven D. James* TELEPHONE NO. (303) 893-2438  
 NAME (PRINT) Steven D. James TITLE Vice President DATE March 29, 1996

(This space for Federal or State office use)

APPROVED *[Signature]* TITLE \_\_\_\_\_ DATE 4/3/96  
 CONDITIONS OF APPROVAL, IF ANY: