



OGCC FORM 4
Rev. 8/89

STATE OF COLORADO
OIL AND GAS CONSERVATION COMMISSION
DEPARTMENT OF NATURAL RESOURCES

SUBMIT ORIGINAL AND 1 COPY



FOR OFFICE USE ONLY			
ET	FE	UC	SE

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)

<input type="checkbox"/> OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> COALBED METHANE <input type="checkbox"/> INJECTION WELL <input checked="" type="checkbox"/> OTHER		5 FEDERAL INDIAN OR STATE LEASE NO.
2 NAME OF OPERATOR WESTERN OPERATING COMPANY		6 PERMIT NO. 71-318
3 ADDRESS OF OPERATOR 518 -17TH ST., SUITE 1680		7 API NO. 05-061-06107
CITY DENVER	STATE CO	8 WELL NAME DAWSON
ZIP CODE 80202		9 WELL NUMBER NO. 6
4 LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 1980' FNL & 1980' FEL OF SEC. 8		10 FIELD OR WILDCAT BRANDON
At proposed prod. zone SAME		11 QTR. QTR. SEC., T.R. AND MERIDIAN SW/4 NE/4 SEC. 8 T19S-R45W
12 COUNTY KIOWA		

Check Appropriate Box To Indicate Nature of Notice, Report or Notification

13A. NOTICE OF INTENTION TO:

- ☒ PLUG AND ABANDON
- ☐ MULTIPLE COMPLETION
- ☐ COMMINGLE ZONES
- ☐ FRACTURE TREAT
- ☐ REPAIR WELL
- ☐ OTHER

VP

13B. SUBSEQUENT REPORT OF:

- ☐ FINAL PLUG AND ABANDONMENT (SUBMIT 3RD PARTY CEMENT VERIFICATION AND JOB LOG)
- ☐ ABANDONED LOCATION (WELL NEVER DRILLED - SITE MUST BE RESTORED WITHIN 6 MONTHS)
- ☐ REPAIRED WELL
- ☐ OTHER

*Use Form 3 - Well Completion or Recompletion Report and Log for subsequent report of Multiple/Commingle Completions and Recompletions

13C. NOTIFICATION OF:

- ☐ SHUT-IN, TEMPORARILY ABANDONED (DATE _____) (REQUIRED EVERY 6 MONTHS)
- ☐ PRODUCTION RESUMED (DATE _____)
- ☐ LOCATION CHANGE (SUBMIT NEW PLAT)
- ☐ WELL NAME CHANGE
- ☐ OTHER

14. DESCRIBE PROPOSED OR COMPLETED OPERATIONS ON THIS FORM (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent)

15. DATE OF WORK

1. Set cmt retainer on top of fish (parted 2-7/8" tbg) @ 2556'±. Mix & pump 200 sxs cmt. Spot 2 sxs on top of cmt retainer.
2. Load csg w/wtr. Spot 10 sx plug @ 1400'±. Let cmt set up.
3. Perf 4 holes in 5-1/2" csg @ 1300' ±. Set cmt retainer @ 1250'. Squeeze 115 sxs cmt through retainer. Spot 2 sxs cmt on top of retainer.
4. Perf 4 holes in 5-1/2" csg @ 194'. Pmp 50 sx plug, 25 sx out 5-1/2" & leave 25 sxs inside 5-1/2" csg.
5. Set 10 sx plug @ sfc. Put 5 sxs in 8-5/8" & 5 sxs in 5-1/2" csg. Cut 8-5/8" & 5-1/2" csg 4' + below ground level. Weld on 3/8" thick cap that reads: Dawson #6, SW NE Sec. 8-T19S-R45W.
6. Reclaim location.

16. I hereby certify that the foregoing is true and correct

SIGNED

TELEPHONE NO. 303/893-2438

NAME (PRINT) STEVEN D. JAMES

TITLE VICE PRESIDENT

DATE

(This space for Federal or State office use)

APPROVED

CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE

8/26/90
PROVIDE 24 HR NOTICE OF MIRR TO BOB VANSTICKLE