

BEST IMAGE  
AVAILABLEWEEKLY REPORT OF COLORADO STATE WELLS  
DAILY DRILLING REPORT

01341766

COLORADO

DIVISION

AS OF 7 A.M. Oct. 18 thru 24

LEASE	WELL NO.	COMMENCED DRILLING	SIZE AND DEPTH LAST STRING CASING SET	FORMATION AND REMARKS	DEPTH YESTERDAY	DEPTH TODAY
Kiowa County White	1	10-4-52	10 3/4" 252'	<p>Oct. 18 and 19 No reports.</p> <p>Oct. 20 Drilling lime 3860'. Cored 3777-3821, recovered 9 1/2' limestone, white, colitic, very porous, bleeding oil, 2' limestone, slightly porous, light stain, 4' limestone hard &amp; dense - no shows, 8' limestone, colitic, porous, some oil stain, brackish smell, 20 1/2' hard dense limestone - no show. DST 3771-3821, open 45 minutes, shut in 15, good blow, recovered 1800' salt water, FP 770#, SIP 960#. DST (straddle packer - TD 3821') packers set 3770-91, open 30 min., shut in 10, good blow, recovered 1170' salt water, FP 570#, SIP 970#. DST packers set 3767-88, open 25 min., shut in 10, recovered 1100' salt water. DST packers set 3773-94, open 60 min., shut in 15, recovered 1890' salt water, FP 800#, SIP 970#.</p> <p>Oct. 21 Drilled to 3892', coring at 3924'.</p> <p>Oct. 22 Cored 3892-3924', recovered 42' - 6 1/2' wet porous lime no show, 34 1/2' dense non-porous lime, 1' porous colitic lime, oil odor &amp; stain. Reamed, coring ahead.</p> <p>Oct. 23 Drilling lime 3960'. Cored 3934-44, recovered 10' - 2 1/2' porous colitic lime bleeding oil, 7 1/2' dense lime. DST 3931-44, open 2 hrs., shut in 15 min., recovered 70' oil-and-gas-cut mud, 200' salt water, FP 120#, SIP 890#.</p> <p>Oct. 24 Drilled to 4080', preparing to core. Mud slightly gas cut.</p>	OCT 27	1952
Kiowa County Strake	1	10-15-52	10 3/4" 262'	<p>Oct. 18 and 19 No reports.</p> <p>Oct. 20 Drilling Red Beds and anhydrite 2615'. Sample tops: Timpus 995', Dakota 1505', Morrison 1755', Persian 2280'.</p> <p>Oct. 21 Drilling Red Beds and anhydrite 3005'.</p> <p>Oct. 22 Drilling shale w/lime streaks 3355'.</p> <p>Oct. 23 Drilling shale 3610'.</p> <p>Oct. 24 Drilling shale 3880'.</p>	285'	2615'
					2615'	3005'
					3005'	3355'
					3355'	3610'
					3610'	3880'

Copies to: J. J. Zorichak - File



WEEKLY REPORT OF COLORADO STATE WELLS  
DAILY DRILLING REPORT

BEST IMAGE  
AVAILABLE

Colorado

DIVISION

AS OF 7 A.M. Week ending Oct. 31

LEASE	WELL NO.	COMMENCED DRILLING	SIZE AND DEPTH LAST STRING CASING SET	FORMATION AND REMARKS	DEPTH YESTERDAY	DEPTH TODAY
<u>COLORADO</u>						
White	1	10-4-52	10 3/4" 252'	Oct. 25 and 26 No reports.  Oct. 27 Drilling shale & lime 4358'. Cored 4080-88, recovered 8' 2 1/2' limestone, porous, bleeding oil & gas, 5 1/2' limestone, top 3' fractured, oil stain in fractures. DST Kansas City 4068-88, open 2 hours, shut in 20 min., recovered 200' oil-and-gas-cut mud, 460' salt water, FP 300#, SIP 920#. Top of Marmaton 4200'.	4080'	4358'
				Oct. 28 Drilling lime 4489'.	4358'	4489'
				Oct. 29 Drilling shale 4634'. Top of Cherokee 4330'.	4489'	4634'
				Oct. 30 Drilling black shale 4768'.	4634'	4758'
				Oct. 31 Drilling lime 4854', Progress 86 Top of Mississippian 4768'.	4758'	4854'
Kiowa County Strake	1	10-15-52	10 3/4" 262'	Oct. 25 and 26 No reports.  Oct. 27 Drilling lime 4440'. Top of Pennsylvanian 4235'.	3880'	4440'
				Oct. 28 TD 4531' in lime. Made two unsuccessful drill stem tests, attempting third.	4440'	4531'
				Oct. 29 Drilling lime 4606'. Could not get packer to hold on third attempt to DST.	4531'	4606'
				Oct. 30 Drilled to 4744', preparing to core.	4606'	4744'
				Oct. 31 Coring at 4794', Progress 50, Tentative Top Kansas City lime 4421'.	4744'	4794'

Copies to: ☒ J. J. Zorichak - File



## DAILY DRILLING REPORT

COLORADO

DIVISION

AS OF 7 A.M. Week ending

NOV 17 1952

November 14, 1952

CONSERVATION COMMISSION

LEASE	WELL NO.	COMMENCED DRILLING	SIZE AND DEPTH LAST STRING CASING SET	FORMATION AND REMARKS	DEPTH YESTERDAY	DEPTH TODAY
<u>COLORADO</u> White	1	10-4-52	10 3/4" 252'	<p>November 8 &amp; 9 - No report</p> <p>November 10 Drilling sandy dolomite 5350'. Sdt 5165-5233', open 45 Minutes, shut in 15, recovered 600' fresh water and drilling mud, FP 250#, SIP 1030#. DST 5115-60, open 90 minutes, shut in 15, recovered 350' fresh water and drilling mud, FP 140#. SIP 1005#.</p> <p>November 11 Drilled to 5418', lost circulation. preparing to run Schlumberger.</p> <p>November 12 TD 5418'. Regained circulation. Conditioning mud to run Schlumberger</p> <p>November 13 Conditioning hole to run Schlumberger. TD 5418'</p> <p>November 14, TD 5418'. Lost and regained circulation. Running Schlumberger</p>	5233'	5350'
Kiowa County Strake	1	10-15-52	10 3/4" 262'	<p>No reports Nov. 8 &amp; 9.</p> <p>November 10 Drilling lime 5983'</p> <p>November 11 Drilled lime to 6018' Attempting to regain lost circulation. Sample top Mississippian 5946.</p> <p>November 12 TD 6018'. Regained lost circulation. Preparing to core ahead.</p> <p>November 13 Cored 6019'-23', recovered 4' brown lime, no straining. Drilled to 6030'. Drill stem testing 5990'-6030'</p> <p>November 14 DST 5090' Open 1 hr. shut in 15 min. recovered 875' mud and fresh water, FP 350, SIP 1135 pounds, Drilled to 6122' and lost returns.</p>	5518'	5983'
					5983'	6018'
					6018'	6018'
					6018'	6030'
					6030'	6122'

Copies to J. J. Zorichak FILE



## DAILY DRILLING REPORT

COLORADO


DIVISION

Week Ending  
AS OF 7 A.M. November 21, 1952

LEASE	WELL NO.	COMMENCED DRILLING	SIZE AND DEPTH LAST STRING CASING SET	FORMATION AND REMARKS	DEPTH YESTERDAY	DEPTH TODAY
COLORADO Kiowa County White	1	10-4-52	10 3/4" 252'	<p>November 15, 16, no report</p> <p>November 17. TD 5418'. Ran Schlumberger to 5405'. Set 30-sack cement plug at 4800'. Cemented 7" casing at 4171 w/200 sacks. Drilled float, cleaned out to 4145. Running Lane-Wells.</p> <p>November 18 TD 5418'. No Progress Drilled float and shoe to 4162'. Conditioned mud. Ran Gamma-Ray. Ran dry test of shoe, coming out of hoel.</p> <p>November 19 TD 5418'. No progress FBD 4162. Ran dry test OK. Released rig 8pm 11/18. (Dropping from report until cable tools are moved in for test.)</p>	5418'	5418'
Strake	1	10-15-52	10 3/4" 262'	<p>November 15, 16, no report.</p> <p>November 17 TD 6123'. Lost circulation. Cemented w/60 sacks, recementing. Progress 1.</p> <p>November 18 TD 6123'. No progress Spotted Burlap, Three 50-sack batches cement Last batch 20' fill-up.</p> <p>November 19 Drilled to 6189' lost circulation. Progress 66'</p> <p>November 20 Regained circulation drilling at 6190' Progress 1'.</p> <p>November 21 Drilled dolomite and lime to 6240', lost circulation. Going in with full returns Progress 49'</p>	6122'	6123'
					6123'	6123'
					6189'	6189'
					6190'	6190'
					6190'	6240'

J.J. Zorichak

FILE

OIL & GAS  
CONSERVATION COMMISSION