




COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS
CONSERVATION COMMISSION

303-1

(Indicate nature of data by checking below)

- Notice of intention to drill _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____ X
- Statement of perforating _____ X
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____
- Report of work done on well since previous report _____ X

Following is a (notice of intention to do work) 12-1 1952
(report of work done) (On land) (patented) described as follows:

<u>Colorado</u> State	<u>Kiowa</u> County	<u>East Eads</u> Field
<u>1</u> (Well No.)	<u>White-Brandon</u> (Lease)	<u>SE/4 Sec. 20</u> (Sec. and 1/4 Sec.)
	<u>19S</u> (Twp.)	<u>45W</u> (Range)
		<u>(Meridian)</u>

The well is located 330 ft. (N) of South and 330 ft. (E) of East
(S) (W)
line

The elevation above sea level is 3,913 ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

- 10-18-52 - D.S.T. 3771-3821 - Open 45 min., Shut in 15, good blow, recovered 1800' salt water FP 770# SIP 960#.
- 10-18-52 - D.S.T. 3770-91 - Open 30 min., shut in 10, good blow, recovered 1170' salt water. FP 570# SIP 970#.
- 10-19-52 - D.S.T. 3767-88 - Open 25 min., shut in 10, recovered 1100' salt water
- 10-19-52 - D.S.T. 3773-94 - Open 60 min., shut in 15, recovered 1890' salt water, FP 800#, SIP 970#.
- 10-23-52 - D.S.T. 3931-44, - Open 2 hrs, shut in 15 min., recovered 70' oil and gas cut mud, 200' salt water, FP 120#, SIP 890#.
- 10-27-52 - D.S.T. 4068-88 - Open 2 hours, shut in 20 min., recovered 200' oil and gas cut mud, 460' salt water, FP 300#, SIP 920#.
- 11-5-52 - D.S.T. 5165-5233 - Open 45 min., shut in 15, recovered 600' fresh water, FP 250#, SIP 1030#.
- 11-5-52 - D.S.T. 5115-60 - Open 90 min., shut in 15, recovered 350' fresh water, FP 140#, SIP 1005#.

CONTINUED ON ATTACHED SHEET

Approved: _____ Company Continental Oil

J.J. Zorich Director Address 1755 Glenarm Place

By [Signature]
Title Asst. Regional Production Mgr.

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.

11-17-52 - Ran Schlumberger to 5405, set 30 sack plug, plugged back to 4800, cemented 7" casing at 4171 w/ 200 sacks. Will perforate five zones from 4138 to 4144; 4067 to 4088; 3918 to 3932; 3798 to 3810; and 3774 to 3792 with four shots per foot to test formations. The two lower zones will be tested together and the three upper zones separately with a bridge plug between zones unless an excessive water flow is encountered. In that event, a squeeze job will be performed.