



Oil will be trucked offsite

Produced water will be trucked offsite

LEGEND	Status	Qty
Wellhead	Permanent	1
Heated Separator 75 bbl	Permanent	1
Water Tank 300 bbl	Permanent	1
Oil Tank 300 bbl	Permanent	1

All gas piped to processing plant and separated there.

## PRODUCTION

Note: The well will be a conventional vertical well with no hydraulic fracturing, stimulation, or flowback. All formation water during well completion and all produced water during production will flow to an on-site separator for separation of oil and water. Oil and water will be stored in tanks. Oil will be trucked to a commercial transfer point. Water will be trucked for disposal at a commercial UIC well. The gas stream will be piped underground to the existing Ladder Creek Gathering System operated by Tumbleweed Midstream for processing off site.

PRELIMINARY PROCESS FLOW DIAGRAM  
Wavetech Helium, Inc.  
**UPRC 1 Eiger 14-11**  
Section 11 T12S R43W