

Ranger Energy Services, LLC
10350 Richmond Avenue Suite 550
Houston, TX 77042
(713) 935-8900
(713) 935-8901 (FAX)



516043

Unit # C1002

Daily Work Ticket

Day #

Customer Name			Customer AFE #	Date:
Chevron			WBS: UWRWE-A2963- ABN Patricia Albidrez	1/24/2023
Mailing Address	City	State	Zip	County
	CO			Weld County, CO

Field	Lease	Well	Order #
		COCKROFT USX A 11-3	
TVD	MD	Calculated Horizontal Length	Company Rep
00	00	0	patricia albidrez

Work Description	
P&A	✓

Sub Code Description	
Cement	✓

Description	Qty	Rate	Disc	Total	Stage
Turnkey Rigless Cement Pump Charge	1.00 @	\$7,520.00	0.00%	\$7,520.00	
Wireline Charge	-1.00 @	\$3,500.00	0.00%	(\$3,500.00)	
Cement Retarder	1.00 @	\$20.00	0.00%	\$20.00	
Water Bobtail Hours	9.00 @	\$90.00	0.00%	\$810.00	
Cement (neat)	35.00 @	\$0.00	0.00%	\$0.00	
Sugar	25.00 @	\$0.00	0.00%	\$0.00	
Water	40.00 @	\$1.00	0.00%	\$40.00	

TOTAL BILLABLE AMT \$4,890.00

Description of Work Start Time 05:00 AM Stop Time 03:00 PM

From	To	Hours	Description	Details	Stage
5:00:47 AM	6:00:47 AM	1	RU/RD cement crew	C1002, MOB to location, spot in, rig up, waited on flowback to incinerate gas, 10:00 AM Status: 2-3/8" 4.7# EOT at 6,897' inside 4-1/2" 11.6# casing, pumped 32 bbl. of freshwater, pumped 1 bbl. LCM pill, displaced with 25 bbl., waited	
6:00:47 AM	7:00:47 AM	1	RU/RD cement crew	30 minutes, established circulation and pumped 96 bbl. total water, pumped 5 bbl. freshwater spacer, mix and pumped	
7:00:47 AM	8:00:47 AM	1	RU/RD cement crew	35 sxs of 15.8# 1.15 cu.ft./sack Class G cement with retarder, 7.2 bbls of slurry, displaced with 25.3 bbl. to cover from	
8:00:47 AM	9:00:47 AM	1	RU/RD cement crew	6,897' to 6,384', PH 7.2 Chlorides: <150 ppm, Temperature: 62F ,RD valve, wash out pump; 1:30 pm, MOB to yard Non rev: pre trip trucks, prep for job	
9:00:47 AM	10:00:47 AM	1	RU/RD cement crew		

Payroll Section					
Employee	Rev Hours	Travel Hours	Non Rev Hours	Total	
Tool Pusher	Rascon, Aron	0.00	0.00	0.00	0.00
Operator	Lopez, Alfonso	7.50	0.00	1.00	8.50
Derrick	Garcia, Rodolfo F.	7.50	0.00	1.00	8.50
FloorHand	Soto, Juan I.	9.00	0.00	2.00	11.00

No Unreported Incidents Per My Signature

Ranger Representative

Customer/Agent