



RECEIVED

JUN 29 1967

No. 1 USA-BUTLER
DRILL STEM TESTS DATA

COLO. OIL & GAS CONS. COMM.

DST # 1

3940-3980'. I.O.-10 min.; ISI-60 min.; F.O.-60 min.; FSI-60 min.
Recovered 40' watery mud, 1700' water.
FP-264-769. SIP-1015-1011. HP-2020-2006.

DST # 2

4845-4883'. I.O.-10 min.; ISI-40 min.; FO-60 min.; FSI-60 min.
Recovered 65' oil cut mud.
FP-30-47. SIP-897-843. HP-2498-2453.

No. 1 USA-BUTLER
ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

<u>Depth Interval</u>	<u>Amount & Kind of Material Used</u>
4732-4799'	1500 gal. of 15% MCA.
4590-4722'	1500 gal. of 15% MCA 11,844 gal. of gelled 15% HCl

No. 1 USA-BUTLER
PERFORATION RECORD

<u>Interval</u>	<u>Size</u>	<u>Number</u>
4590, 4592, 4598, 4600, 4602, 4612, 4614, 4616, 4618, 4628, 4630, 4632, 4642, 4644, 4646, 4648, 4654	0.45"	17
4660-73	0.45"	14
4677-97	0.45"	21
4702-4716	0.45"	15
4721-22	0.45"	2
4732-37	0.45"	6
4739-42	0.45"	4
4745	0.45"	1
4748-50	0.45"	3
4752-71	0.45"	20
4779-81	0.45"	3
4785-92	0.45"	8