



J. W. GIBSON WELL SERVICE CO.

TO: Whiting Petro. Corp.

FROM: J.W. Gibson Well Service - Cheyenne Wells

DATE: 7-8-93

Well Lease - U.S.A. Bulter #1

Mix and spot 50 sx cement at 3895'+
Mix and spot 50 sx cement at 1535'+ Tag plug - 1100'
Perf. csg at 1050'+. Set retainer at 1040'+.
Squeeze 40 sx cement thru retainer at 900 psi.
Mix and spot 20sx cement on top of retainer at 1040'+.
Cut csg at 205'=. Pull 6 jts csg.
Mix and spot 50sx cement at 205'+.
Mix and circulate 25 sx cement 50' to surface.
Dig out and cut off surface csg 4' below GL.
Weld on 1/4" steel plate. With USA Bulter #1 SW NE SEC 10 T195-R45W.
Fill in hole.

235 sx total of cement.

OK *[Signature]*
Tom Patten- Operator

Toby Eisenach- Area Manager

Toby S. Eisenach