



T I G H T H O L E K E E P C O N F I D E N T I A L F O R S I X (6) M O N T H S

DST RECORD FOR No. 1 HARRISON

DST # 1 4726-4766' K.B. 40'

IO 6 min. w/ vy wk blow, ISI 60 min., open 30 min. w/ zero blow - by passed tool - open 2 hrs. w/ continuing weak blow (tool open $2\frac{1}{2}$ hrs. on 2nd open), FSI 2 hrs. IHP 2476 #. 1st FP 10-24#, ISIP 884#, 2nd FP 19-117#, FSIP 873#, FHP 2432#, Rec. 124' gas in drill pipe, 56' oil sli mc, 60' ocm, 180' vy sli ocm for a total of 296' of fluid. Oil API grav. measured as 37.1° @ 60°F .

DST # 2 4766-4793' K.B. 27'

IO 5 min. w/ fair blow, ISI 60 min., open 2 hrs. w/ zero to increasing good blow - leveled off last $\frac{1}{2}$ hr. FSI 3 hrs. IHP 2412#, 1st FP 19-27, ISIP 892#, 2nd FP 24-163#, FSIP 877#, FHP 2401#. Rec. 62' of gas in drill pipe, 52' of free oil, 106' of sli mco, 214' hocm for a total of 372' total fluid. Oil API grav. 37.1° @ 60°F - Funnel vis. was 40 sec.

DST # 3 4855-4584' K.B. 29'

IO 6 min. w/ immediate fair blow, ISI 64 min., open 90 min. w/ vy faint blow almost immed - blow gradually increased thruout test to good. FSI 2 hrs. IHP 2556#, 1st FP 17-51#, ISIP 921#, 2nd FP 42-247#, FSIP 910#, FH 2452#. Rec. 60' of gas in DP + 537' of o & wtr. cm fairly well oil cut @ top decreasing to 1% oc @ bottom w/ increasing wtr. cut.

DST # 4 4892-4903' K.B. 11'

IO 5 min. w/ good blow, ISI 60 min., open 90 min. w/ good blow thruout test. FSI 123 min., IHP 2573#, 1st FP 31-115#, ISIP 948#, 2nd FP 102-508#, FSIP 935#, FHP 2500#. Rec. 1269' of wtr. sli mc @ topgrading to almost clear wtr. @ bottom.

Note: above calculated on bottom gauge

DST # 5 4931-5040' K.B. 109'

IO 6 min., w/ immed. strong blow, ISI 60 min., open 63 min. w/ good blow thruout test. NGTS, FSI 60 min., IHP 2514#, 1st FP 204-368#, ISIP 953#, 2nd FP 342-866#, FSIP 950#, FHP 2510#. Rec. 636' wtr. cm & 1269' sli mc wtr. or 1905' of fluid.

DST # 6 4686-4720' K.B. 34' straddle test

IO 6 min. w/ a vy wk blow, ISI 60 min., 2nd FP 60 min. w/ no blow - flushed tool after 15 min. - no blow thruout test. FSI 60 min., IHP 2411#, 1st FP 18-30#, ISIP 889#, 2nd FP 24-66#, FSIP 847, FHP 2392#, Rec. 84' vy sli gassy oil cut mud.