


COLORADO OIL AND GAS COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

- Notice of intention to drill (attach plat) _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____
- Report of work done on well since previous report _____

Locate Well Correctly

		16	
	x		

Notice to do work
Report of work done

Land: Fee and Patented
State

Lease No. 116550

Colorado State Washington County Big Beaver Field
8 (Well No.) State-Colorado "B" (Lease) 75' east of 11 (Sec.) 3S (Twp.) 56W (Range) 6th P.M. (Meridian)

The Well is located 660 Ft. (N) of Section Line and 2055 Ft. (E) of Section Line. (~~SW~~)

The elevation above sea level is 4706.5 Ft. RDB.

Details of Plan of Work: (State names of and expected depths to objective sands. Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Stanolind drilled subject well to total depth of 5161, PBD 5133.

Unable to obtain commercial production from well. Pulled tubing and temporarily abandoned 1-5-56.

Proposed 5 1/2" casing recovery program: Dump sufficient amount of sand into casing to fill well, minimum of 20 feet above all perforations. Five sacks cement will be set on top of sand with dump bailer. Casing will be shot off and pulled, with maximum recovery possible.

Proposed plugging program: Well will be plugged as follows: 5 sx cement at surface casing shoe, 10 sx cement at surface. Location will be cleaned, leveled and restored to original contour.

Approved: _____

JAN 13 1956

[Signature]
Director

AJJ	
DVR	
FJK	
WRS	
WHM	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

Date January 10, 1956

Company Stanolind Oil and Gas Company

Address Brush, Colorado

By A. G. Wilburn

Title Field Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.