


COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS
CONSERVATION COMMISSION

(Indicate nature of data by checking below)



- Notice of intention to drill (attach plat) _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____
- Report of work done on well since previous report
- Subsequent notice to abandon well

Locate Well Correctly

		16	
	x		

Notice to do work Land: Fee and Patented
 Report of work done State Lease No. 116550

Colorado State Washington County Big Beaver Field
8 State Colorado "B" 75' E of 16 3S 56W 6th PM
 (Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 660 Ft. (N) of Section Line and 2055 Ft. (E) of
 (S) (W)
 Section Line.

The elevation above sea level is 4706.5 Ft. RDB:

Details of Plan of Work: (State names of and expected depths to objective sands. Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Stanolind drilled subject well to TD of 5161 ft., PDB 5133 ft. unable to obtain commercial production, well spudded 11-18-55, well plugged and abandoned 2-14-56.

188 ft of 8-5/8" 29.35# 8VII LW LP cemented in hole w/ 175 sacks and abandoned in hole.

- Well plugged as follows: West Supply Company, Inc. moved in unit and pulled 3790' of 5 1/2" 14# 8-RT J-55 casing and 1- fill well bore with 1 yard sand.
- 2- run 5 sack regular cement plug on top of sand w/ dump bailer.
 - 3- Run 5 sack regular cement plug at bottom of surface casing.
 - 4- Run 10 sack regular cement surface plug.

AJJ	
DVR	
FJK	
WRS	
HHM	
AH	
JJD	✓
FILE	

Location cleaned and leveled and restored to original contour.

171-05562



Approved: APR 17 1956

A. J. Gersin
Director

Date April 16, 1956

Company Stanolind Oil and Gas Company

Address Brush, Colorado

By A. C. Wilson

Title Field Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.