




**OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO**



OIL & GAS
CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐

Notice of Intention to Change Plans ☐

Notice of Intention to Abandon Well ☐

Report of Remedial Work ☐

☒ Report of Recompletion ☒

Other ☐

(Check appropriate space)

LEASE NAME State Colorado "B"

WELL NO. 7

FIELD Big Beaver

WILDCAT

COUNTY Washington

LOCATION C SW SW

(Quarter Quarter)

Section 16

Township 3S

Range 56W

Meridian 6th

660

feet from N

N or S

Section Line and

660

feet from E

E or W

Section Line

(DETAILS OF WORK)

Well was sand pumped to 5130' and interval 5045'-50' (J-2 bench) was perforated with 4 JSPP. Casing scraper was run on tubing past all perforations and then retrievable bridge plug was set at 5056' RDB. Well was swabbed from 4000' for 10 hours, received 13 barrels water per hr. Recovered bridge plug and perforated interval 5104'-09' (J-4 bench) with 4 JSPP. Well was sand pumped to 5127'-32' and packer was set at 5090' RDB. Swabbed well interval 2200' down to 3800', received 6 barrels ~~water~~ water and 93 barrels new water. Pulled rods and tubing, well temporarily shut in pending further stimulative work. Production prior to workover 12 BOPD, 588 BWPD.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

FEB 26 1960

Date

Director

Company Pan American Petroleum Corp. Date Feb. 23, 1960

Address Box 1031, Kimball, Nebraska Phone No. BE 5-4603

By G. A. Wilson Title Area Supt.

(Signature) G. A. Wilson

3 ✓