



HALLIBURTON
ENERGY SERVICES

JOB LOG FOR

00333508

DATE

12-15-93

PAGE NO.

1

CUSTOMER

CARL A HOAY

WELL NO.

#3

LEASE

BLOOMENKAMP

JOB TYPE

PLUG TO ABANDON

TICKET NO.

525807

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0900							CALLED OUT
	0930							ON LOCATION, SAFETY MEETING
								RIG UP
	1000		.5					LOAD TBG PKR SET
		.25	4				3450	PRESSURE WELL RECEIVED
							2200	BRACKEN
							2600	INJECT
	1030	3	9				4000	WELL LOCKED W/ OIL & GAS COND. COMM.
							3200	BLEED OFF
	1045	1	.5				4000	INJECT, & LOCK UP
	1050							RELEASE PRESSURE
								RELEASE & TRIP OUT W/ PKR.
								TRIP IN W/ TBG OPEN ENDED
	1100							TO PLUG IN 5 1/2" CS. W/ 30 SK
								CMT W/ .5" NR-5, 4681 FT TO 4946 FT
	1400	3	5					EST CIRC W/ FRESH H ₂ O CLEAR TBG
	1405	3	6					MIX & PUMP 30 SK CMT 15.6 GAL
	1420	3	20					DISPLACE W/ FRESH WATER
								PULL TBG, CHLOTT WIRE LINE
								CUT OFF @ SURF. PULL CS
								11 1/2" T&L
	1430							CRAW RELEASED RTN TO LOC
								12-15-93 AM
12-16	0900							CALLED OUT
	0900							ON LOCATION, SAFETY MEETING, RIG UP
	1100		3					CLEAR TBG W/ WATER PLUG IN 5 1/2" CS. TO 120 FT
	1110							97 FT IN SURF CS. 23 FT OPEN HOLE
	1110		9					PUMP 45 SK CMT W/ 34 CS. 2
	1120		.5					DISPLACE W/ FRESH WATER
								PULL OUT OF PLUG W/ TBG
								CUT OFF SURF HEAD - 5"
								DUMP CMT & CAP
	1200							TALKS & CRAW RELEASED

CUSTOMER