

WELL NAME:	ROSS 8-60 18-07-02					OPERATOR:	CIVITAS NORTH	
FIELD:	WILDCAT					FORMATION:	Niobrara	
SHL:	gtr-qtr	SESW	Section	18	Township	8N	Range	60W
BHL:	gtr-qtr	LOT 1	Section	7	Township	8N	Range	60W
COUNTY:	WELD		STATE:	CO		API:	05-123-51394-00	

not to scale	
GROUND LEVEL:	4950
KELLY BUSHING:	4974
SPUD DATE:	5/13/2022
TD DATE:	6/12/2022

9-5/8" csg @  
1,964

CONDUCTOR CASING

SIZE:	16
WEIGHT:	43#
HOLE SIZE:	26
CSG DEPTH:	104

SURFACE CASING

SIZE:	9-5/8"
WEIGHT:	36#
HOLE SIZE:	13-1/2"

HOLE DEPTH:	1,964
CSG DEPTH:	1,964
CEMENT:	600 SKS

TOC:	SURFACE
------	---------

PRODUCTION CASING

SIZE:	5-1/2"
WEIGHT:	17#
HOLE SIZE:	8-1/2"
TOTAL DEPTH TVD	6,496
TOTAL DEPTH MD	15,703
CSG DEPTH:	15,703
CEMENT:	2490 SKS

TOC:	982
------	-----

PRODUCTION TUBING

SIZE:	2 3/8"
WEIGHT:	4.7#

DEPTH:	6,663
--------	-------

PACKER DEPTH:	6,662
---------------	-------

FRAC DATA

481,920	BBLS GELLED FLUID
606	BBLS ACID
16,175	BBLS FRESH WATER
498,701	BBLS TOTAL FLUID

FORMATION TOPS & PERFORATIONS

NIOBARRA MD	6,452
-------------	-------

PERFORATIONS	6,972	15,640
--------------	-------	--------

0	# 30/50 MESH
13,663,551	# 40/70 MESH
609,240	# 100 MESH
14,272,791	# TOTAL SAND

50	STAGES
----	--------

EOT @ 6663

Production Csg @ 15703'

MD TD 15,703

50 49 48 47 46 45 44 43 42 41 40 39 38 37 36 35 34 33 32 31 30 29 28 27 26 25 24 23 22 21 20 19 18 17 16 15 14 13 12 11 10 9 8 7 6 5 4 3 2 1