

This final reclamation plan is being submitted as a follow-up to the onsite with the Bureau of Land Management and Wexpro Company, held on 10/19/22, in regards to the reclamation status of the well pad and associated ROW's.

While final reclamation of this well pad has taken place, due to existing, active lines traversing the well pad, re-contour work cannot be completed until the gathering lines are abandoned, as to not continue to create disturbance of the area. Due to the existence of the previously abandoned gathering line traversing the well pad (see attachment), Wexpro Company is currently working with the BLM ROW Specialist and Andeavor (gathering owner at time of abandonment) to remove the shallow line and allow for proper recontouring of the area. Andeavor's line removal is expected to be completed in 2023.

Areas of concern during onsite:

- Well pad is to be/has been treated for noxious weeds and cheatgrass in 2022 and subsequent years by Wexpro Company's weed spraying contractor.
- Trash and debris of concern (anchor) have been removed from the area by field personnel.
- Riser and loop stop to be removed by Andeavor, as part of the previous associated line abandonment.
- All gathering lines are in a Right of Way (see attachment).
- "Pit/Pond" identified on southern edge of well pad is not actually a Wexpro Company pit or facility. There were two pits on this well pad: COGCC facility 100701 & 100700. Facility 100701 has been closed by COGCC. Wexpro is currently working with COGCC to obtain closure for facility 100700.

Final reclamation Plan: The well pad will be reclaimed as follows: Shallow gathering lines will be removed to allow for proper recontouring of the well pad.

Any gravel or road base will be removed from the pad area and placed on an existing access road in the Powder Wash field. Culverts in roads or drainages will be removed and disposed of. Topsoil from the pad will be removed and stockpiled. The disturbed area will be recontoured to match the surrounding terrain. After recontouring has been completed the topsoil will be spread evenly over the disturbed area and ripped in preparation for seeding.

Please see the attached proposed seed mix. Seed will be drill seeded. The area will be crimped with straw mulch, from a commercial weed free source, for moisture retention.

Fencing of the reclaimed area will be completed, if required by the BLM.

All reclaimed areas will continue to be treated for noxious weeds until Final Abandonment. Pesticide Use proposals will be submitted to the BLM for approval, via Wexpro Company's contractor, prior to any chemical treatments.

The well pad will be monitored annually until approval of Final Abandonment. Reclamation monitoring will be documented in an annual reclamation report submitted to the Authorized Officer by December 31. The report will document compliance with all aspects of the reclamation objectives and standards, identify whether the reclamation objectives and standards are likely to be achieved in the near future without additional actions, and identify actions that have been or will be taken to meet the objectives and standards. The report will also include acreage figures for Initial Disturbed Acres, Successful Interim Reclaimed Acres, and Successful Final Reclaimed Acres. Annual reports will not be submitted for sites

approved by the Authorized Officer in writing as having met interim or final reclamation standards. Any time 30 percent or more of a reclaimed area is re-disturbed, monitoring will be reinitiated. The Authorized Officer will be informed when reclamation has been completed, is successful, and the site is ready for final inspection, having met the LSFO Reclamation Standard.

