



Oil and Gas Conservation Commission

DEPARTMENT OF NATURAL RESOURCES

SUNDRY NOTICE

This form is to be used for general, technical and environmental sundry information. For proposed or completed operations, describe in full on Technical Information Page (back of this form).

RECEIVED NOV 22 1996. Includes checkboxes for ET, OE, PR, ES.

1. OGCC Operator Number: 36980
2. Name of Operator: H & R Well Services, Inc.
3. Address: 17509 County Road 14
4. Contact Name & Phone: Dave Rebol
5. API Number: 05-121-5495
6. OGCC Lease No: 54853
7. Well Name: WFU
8. Location: NE SW 19-3S-55W
9. County: Washington
10. Field Name: Westfork

Complete the Attachment Checklist

Attachment Checklist table with columns for Oper and OGCC, and rows for Survey Plat, Directional Survey, Surface Equipment Diagram, Technical Information Page, Other.

General Notice

12. General Notice section with checkboxes for: Change well name, Change of location, Abandoned Location, Well first shut in, Well resumed production, Request for Confidential Status, Final reclamation, Change of Operator, Spud Date.

Technical Engineering/Environmental Notice

13. Technical Engineering/Environmental Notice section with checkboxes for: Notice of Intent, Report of Work Done, Commingle Zones, Request to Vent or Flare, E&P Waste Disposal, etc.

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct, and complete.

Print Name: Dave Rebol
Signed: [Signature] Title: V.P. Date: 11/10/96

OGCC Approved: [Signature] Title: SR. PETROLEUM ENGINEER Date: DEC 16 1996

CONDITIONS OF APPROVAL, IF ANY: Please submit final P+A on a Form 6

1. Operator Number: 36980	2. API Number: 05- 121-5495
3. Name of Operator: H & R Well Services, Inc.	
4. Well Name: WFU	Number: 10
5. Location (QtrQtr, Sec, Twp, Rng, Meridian): NE SW 19-3S-55W	

This form is to be completed whenever a Sundry Notice is submitted requiring detailed report of work to be performed or completed. This form shall be transmitted within thirty (30) days of work completed as a "subsequent" report and must accompany Form 4, page 1.

FOR OGCC USE ONLY

RECEIVED
NOV 22 1988

ET	OE	PR	ES
----	----	----	----

6.

DESCRIBE PROPOSED OR COMPLETED OPERATIONS

Set CIBP @ 4850' & 2 sxs cement ✓
Pull 5½" casing from 2708' ✓
40 sxs cement @ base of 8-5/8 from 345' up ✓
10 sxs surface plug ✓
Cut off 4' below ground level and weld on cap
Restore surface location



H & R WELL SERVICES, INC.
17509 COUNTY ROAD 14
FT. MORGAN, CO 80701
(970) 867-9007

October 30, 1996

Mr. Frank Hutto
H & R Well Services, Inc.

Re: WFU #10
Washington County, Colorado

Dear Sirs:

We performed the following work on the above lease. This letter should be attached to a Form 4 and forwarded to the Colorado Oil and Gas Commission.

Set CIBP @ 4850' & 2 sxs cement
Pulled 5-1/2" casing from 2708'
40 sxs cement @ base of surface 8-5/8 from 345' up.
10 sx @ surface.
Cut off wellhead and weld plate 4' below ground level.
Restore surface location.

All cement was 50/50 poz, yield is 1.26 cu. ft./sack, weight is 15.1 ppg.

Sincerely,

David Rebol
Vice-President