

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO

99999999

## PLUGGING RECORD

121-05638



## INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Champlin Oil & Refining Co. & Republic Natural Gas Co. Field Ramp Wildcat  
Lease Name Chas. L. Jolly Well No. B-1 County Washington  
Location C-SW-SE Section 7 Township 3-S Range 55-W Meridian 6th  
(Quarter Quarter)  
660 feet from S Section line and 1980 feet from E Section Line  
Nor S E or W

TOTAL DEPTH 5070'DATE OF PLUGGING 6-16-58

## DETAILS OF WORK

1. Set  $4\frac{1}{2}$ " O. D. 9.5# J-55 casing at 5065.84' and cemented with 85 sacks Pozmix A 50-50.
2. Perforated with  $6\frac{1}{2}$ " bullets/ft 4962 to 4971. 54 bullets total.
3. Treated with 25 gals Apted 300 and 40 gals. Fre-flo.
4. Treated with 10,000 lbs sand in 10,000 gals. refined oil.
5. Acidized with 500 gals. 7 $\frac{1}{2}$ % MCA.
6. Treated with 10,000 lbs. sand in 10,000 gals. refined oil.
7. Placed 5 sack cement plug 4935' to 4985'.
8. Shot  $4\frac{1}{2}$ " O. D. 9.5 lb; J-55 casing at 4231'.
9. Pulled 4231' of  $4\frac{1}{2}$ " O. D. casing from well. Left  $4\frac{1}{2}$ " O. D. casing in well from 4231' to 5065.84'.
10. Placed 10 sk cement plug from 78' to 105'. Left 7" O. D. 20 lb. J-55 surface casing in well. Surface casing from 2' below ground level to 98.33'. Surface cemented with 55 sacks Pozmix A 50-50.
11. Placed 5 sk cement plug from 2' below ground level to 18'.
12. Well Plugged and Abandoned 10:30 P.M. - 6-16-58.



00862084

AJJ	
DVR	
WRS	
HHM	
JAM	<input checked="" type="checkbox"/>
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JUN 18 1958

Director

Company Champlin Oil & Refining Co. Date 6-17-58Address Box # 451; Sidney, Nebraska Phone No. 4551By J. F. Rankin Title Dist. Engineer  
(Signature)