

RECEIVED  
AUG 21 1985



D GAS CONSERVATION COMMISSION  
DEPARTMENT OF NATURAL RESOURCES  
OF THE STATE OF COLORADO

File in duplicate for Patented and Federal lands.  
File in triplicate for State lands.

COLO. OIL & GAS CONS. COMM.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND NUMBER Patented	
2. NAME OF OPERATOR Conoco Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR 907 North Poplar, Casper, WY 82601		7. UNIT AGREEMENT NAME	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 1980' FNL & 1980' FWL, SE/NW At proposed prod. zone Same		8. FARM OR LEASE NAME Duvall et al	
14. PERMIT NO.		9. WELL NO. 1	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 4692' GR		10. FIELD AND POOL, OR WILDCAT Big Beaver/J-2 Sand	
		11. SEC., T., E., M., OR BLK. AND SURVEY OR AREA Sec 9, T3S, R56W	
		12. COUNTY Washington	
		13. STATE CO	

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON <input checked="" type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) <input type="checkbox"/>	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work September 1, 1985  
Conoco proposes to plug and abandon this well as follows:

1. POOH w/rods, pump and tubing.
2. RIH to 5090' and fill hole w/9.0 ppg mud.
3. Pump 25 sacks class 'G' Cement in J-2 perfs. Cement will cover at least 50' over top of perfs.
4. Cut 5 1/2" casing @2,000', POOH.
5. Spot 50 sack cement plug from 100' below casing cut to at least 75' above cut.
6. Cut 10 3/4" casing @ 6' below surface.
7. Spot 70 sack cement plug from 75' below surface casing to surface.
8. Weld a 1/4" x 10 3/4" plate on top of casing stub.
9. Install regulation dry hole marker.

The disturbed surface area will be reclaimed to the satisfaction of the landowner as soon as weather permits. A sundry notice will be filed upon completion of abandonment procedures.

18. I hereby certify that the foregoing is true and correct

SIGNED <u>OC Thompson</u>	TITLE <u>Administrative Supervisor</u>	DATE <u>August 14, 1985</u>
(This space for Federal or State office use)		
APPROVED BY <u>William R. Smith</u>	TITLE <u>DIRECTOR</u>	DATE <u>AUG 23 1985</u>
CONDITIONS OF APPROVAL, IF ANY: COGCC (3) BLM - Canon City (2) SCE File		

WRS
FJP
HHM
<input checked="" type="checkbox"/>
RCC
LAR <u>rb</u>
COM
ED