




COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

- Notice of intention to drill (attach plat) _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____
- Report of work done on well since previous report

Locate Well Correctly

	x		
		9	

Notice to do work Land: Fee and Patented
 Report of work done State Lease No. _____

Colorado State Washington County Big Beaver Field

2 (Well No.) Duvall et al (Lease) NE NW 1/4 (1/4 Sec.) 9 (Sec.) 3S (Twp.) 56W (Range) 6th PM (Meridian)

The Well is located 660 Ft. (N) of Section Line and 1980 Ft. (E) of Section Line. (S) (W)

The elevation above ~~sea level~~ ^{Ground} is 4688 Ft.

Details of Plan of Work: (State names of and expected depths to objective sands. Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Drilled to TD of 5179'. Cemented 10 3/4" casing at 95'. DST #1 (1st Bench "J" Sand) 5084-5114', tool open 1 hr., SI 15 minutes, gas to surface in 5 minutes, rec. 50' gas cut mud and water, 2700' water. FP 1240#, SIP 1255#. DST #2 (2nd Bench "J" Sand) 5148-79', tool open 90 minutes, SI 15 minutes, rec. 2450' water, FP 1100#, SIP 1195#.

Well was plugged in the following manner: Ran 70 sack cement plug from 4920-5176', 15 sack cement plug bottom of surface casing, 5 sack cement, with marker, at top of surface casing. Intervals between plugs were filled with heavy mud.

Approved: JAN 12 1955

A. J. Jersin
Director

Date 1-10-55

Company Continental Oil Company
Address 1755 Glenarm
Denver, Colorado

By A. Roberts

Title District Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.

Handwritten note: p 40