




OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐

Report of Remedial Work ☒

Notice of Intention to Change Plans ☐

Report of Recompletion ☐

Notice of Intention to Abandon Well ☐

Other ☐

(Check appropriate space)

LEASE NAME Pierce WELL NO. 2

FIELD Big Beaver WILDCAT COUNTY Washington

LOCATION SE SW Section 9 Township 3S Range 56W Meridian 6 PM
(Quarter Quarter)

660 feet from S Section Line and 1980 feet from W Section Line
N or S E or W

(DETAILS OF WORK)

Pierce Well No. 2 was treated on April 26, 1961. The perforations in the "J" sand from 4950' to 4984' GLM were sand-fraced with 10,000 pounds of 20-40 mesh sand in 7,000 gallons of lease crude oil and 500 pounds of 8-12 mesh aluminum pellets in 5,000 gallons of lease crude oil. A total of 1,400 pounds of ADOMITE MARK II fluid loss additive was also used in the treatment.

Initial production tests after recovering load fluid indicate an increase of 70 to 80 barrels oil per day.

AJJ	
DYR	
WRS	
HMM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

MAY - 3 1961

Date

Director

Company Continental Oil Co. Date 5-2-61
P.O. Box 811,
Address Fort Morgan, Colorado Phone No. UN 7-2495

By C. E. Robertson Title Dist. Supt.
(Signature)