

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

RECEIVED

JUL 5 1968

COLO. OIL & GAS CONS. COMM.

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Continental Oil Company Field Big Beaver Wildcat
Lease Name Pierce Well No. 2 County Washington
Location C/SE -SW Section 9 Township 3 S Range 56 W Meridian C
(Quarter Quarter)
660 feet from S Section line and 1980 feet from W Section Line
N or S E or W

TOTAL DEPTH ORIG. T. D. 5070' P. B. D. 4980' DATE OF PLUGGING 6-18-68

DETAILS OF WORK

This well was plugged and abandoned on June 18, 1968 as follows:

Set 5½" Baker Mercury Model "K". Cement Bridge plug @ 4200 with tubing. Squeezed 100 sx reg. cement thru Model "K" with tubing into perfs. Squeeze pressure 1500 PSI. Job done by Halliburton Company. Rig up jacks - run tension to shoot pipe. Shot pipe at 3,716'. Pulled 117 joints of 5½" casing. Filled hole with heavy mud. Set 15 sx plug at base of surface from 85' to 40'. Filled hole with heavy mud. Set 10 sx plug at surface. Cut casing to 2' below ground level. Welded plate on top of surface casing. Welded 4" marker on top of plate.

DVR	
FJP	
HHM	✓
JAM	✓
JJD	✓

P&A Oil well

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JUL 9 1968Director CO & GCC (2) WCB RCBCompany Continental Oil Company Date 7-3-68

200 N. Wolcott

Address Casper, Wyoming Phone No. 234-7311By J. T. Libben Title Adm. Sec. Chief

(Signature)