

Ranger Energy Services, LLC  
 10350 Richmond Avenue Suite 550  
 Houston, TX 77042  
 (713) 935-8900  
 (713) 935-8901 (FAX)



530254

Unit # C1003

Daily Work Ticket

Day #

<b>Customer Name</b>	<b>Customer AFE #</b>	<b>Date:</b>
Chevron	WBS: UWRWE-A2841- ABN Patricia Albidrez	3/3/2023

<b>Mailing Address</b>	<b>City</b>	<b>State</b>	<b>Zip</b>	<b>County</b>
	CO			Weld County, CO

<b>Field</b>	<b>Lease</b>	<b>Well</b>	<b>Order #</b>
TVD	MD	STATE SCHMIDT 36-45	
00	00	0	00
		<b>Calculated Horizontal Length</b>	<b>Company Rep</b>

<b>Work Description</b>	
P&A	<input checked="" type="checkbox"/>

<b>Sub Code Description</b>	
Cement	<input checked="" type="checkbox"/>

<b>Description</b>
Turnkey Rigless Cement Pump Charge
Wireline Charge
Cement Retarder
Water Bobtail Hours
Water
Cement (neat)
Sugar
Calcium Chloride

**Description of Work**    **Start Time** 05:30 AM    **Stop Time** 07:00 PM

From	To	Hours	Description	Details	Stage
5:30:08 AM	6:30:08 AM	1	RU/RD cement crew	C1003, MOB to location, had delays due to muddy conditions on location, equipment had to get catted in/out, spot in, RU, started	
6:30:08 AM	7:30:08 AM	1	RU/RD cement crew	pumping at 1:50 pm, Status: 2-3/8" 4.7# EOT at 7,010' in 4-1/2" 11.6#, pumped 33 bbl. of fresh, 1 bbl. LCM pill, displaced 26.3 bbl.,	
7:30:08 AM	8:30:08 AM	1	RU/RD cement crew	wait 30 min, established circulation, pumped 110 bbl. total, pumped 5 bbl. fresh, 35 sxs of 15.8# 1.15 cu.ft./sack Class G cement	
8:30:08 AM	9:30:08 AM	1	RU/RD cement crew	w/retarder, 7.1 bbl. of slurry, displaced 25.8 bbl. to cover from 7,010' to 6,497', Water details: PH 7.0, Chlorides: <150 ppm, Temp: 53F,	
9:30:08 AM	10:30:08 AM	1	RU/RD cement crew	RD valve, wash out, 5:30 pm RDMO, Non rev: pre trip trucks, prep for job, post trip trucks.	

Payroll Section					
Employee	Rev Hours	Travel Hours	Non Rev Hours	Total	
Tool Pusher	Rascon, Aron	0.00	0.00	0.00	0.00
Operator	Diaz, Luis M.	13.00	0.00	0.50	13.50
Derrick	Meza, Abraham	13.00	0.00	0.50	13.50
FloorHand	Soto, Juan I.	13.00	0.00	0.50	13.50

**No Unreported Incidents Per My Signature** \_\_\_\_\_