



H&R Well Services, Inc.  
17509 Rd 14  
Ft. Morgan, Colorado 80701  
303-432-5285 or 654-1600 (metro)

December 29, 1990

Mr. Larry Robbins  
Colorado Oil and Gas Commission  
1580 Logan, Ste 380  
Denver, Colo 80202

Operator: H&R Well Services, Inc.  
Lease: West Fork Unit #6  
Washington County, Colo  
SE NW Sec 19 - 3S - 55W

Mr. Robbins,

We performed the following work on the above lease. This letter should be attached to a Form 4 as a cement verification, and forwarded to the Colorado Oil and Gas Commission.

Set a CIBP and 3 sacks above perfs at 4,800'.  
Loaded the hole.  
Cut and pulled casing from 3100'.  
Laid down casing to base of surface at 71', and spotted 35 sacks  
1/2 in and 1/2 out.  
Set 10 sacks at surface.  
Cut wellhead off 4' down.  
Welded a plate.  
Backfilled the hole.

**RECEIVED**

JAN 14 1991

COLO. OIL & GAS CONS. COMM

Sincerely,

Dave Rebol  
H&R Well Services, Inc.