



H&R Well Services, Inc.
17509 Rd 14
Ft. Morgan, Colorado 80701
303-432-5285 or 654-1600 (metro)

December 29, 1990

Mr. Larry Robbins
Colorado Oil and Gas Commission
1580 Logan, Ste 380
Denver, Colorado 80202

Operator: H&R Well Services, Inc.
Lease: West Fork Unit #14
Washington County, Colorado
SE SW Sec 19 - 35 - 55W

Mr. Robbins,

We performed the following work on the above lease. This letter should be attached to a Form 4 as a cement verification, and forwarded to the Colorado Oil and Gas Commission.

Set a CIBP and 3 sacks above perfs at 4,800'.
Loaded the hole.
Cut and pulled casing from 2100'.
Laid down casing to base of surface at 86', and spotted 35 sacks
1/2 in and 1/2 out.
Set 10 sacks at surface.
Cut wellhead off 4' down.
Welded a plate.
Backfilled the hole.

Sincerely,

Dave Rebol
H&R Well Services, Inc.

RECEIVED

JAN 14 1991

STAMP