

RECEIVED

OGCC FORM 4



00325726

STATE OF COLORADO
OIL AND GAS CONSERVATION COMMISSION
DEPARTMENT OF NATURAL RESOURCES

NOV 22 1989

COLO. OIL & GAS CONS. COMM.

File in duplicate for Patented and Federal lands.
File in triplicate for State lands.

FOR OFFICE USE			
ET	FE	UC	SE
		ED	

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION & SERIAL NO.	
2. NAME OF OPERATOR Walter V. Berry		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR 1019 8th Street, Suite 301, Golden, CO 80401		7. UNIT AGREEMENT NAME West Fork	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface		8. FARM OR LEASE NAME	
At proposed prod. zone		9. WELL NO. #1	
14. PERMIT NO.		10. FIELD AND POOL, OR WILDCAT West Fork	
15. ELEVATIONS (Show whether DF, RT, GR, etc.)		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA NWNW Sec. 19-3S-55W	
		12. COUNTY Washington	
		13. STATE CO	

16. Check Appropriate Box To Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

☐
☐
☐
☐

PULL OR ALTER CASING

☐
☐
☐
☐

FRACTURE TREAT

MULTIPLE COMPLETE

SHOOT OR ACIDIZE

ABANDON

REPAIR WELL,

CHANGE PLANS:

(Other)

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

☐
☐
☐
☐

REPAIRING WELL

ALTERING CASING

FRACTURE TREATMENT

ABANDONMENT*

SHOOTING OR ACIDIZING

☐
☐
☒
☐

(Other)

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

18. Date of work 10/21/89

* Must be accompanied by a cement verification report.

Dumped sand to cover the perforations.
Dumped 5 sx of cement, tagged sant at 4700' w/bailer.
Loaded the hole, cut csg. at 1600'.
Set 25 sx cement 1/2 in and 1/2 out of surfact at 60'.
Set 5 sx at surface.
Cut the wellhead off 4'down and welded a plate.
Backfilled the hole and dug the deadmen.

(See attached letter from H & R Well Services, Inc.)

19. I hereby certify that the foregoing is true and correct

PRINT Michael G. Cruson

SIGNED *[Signature]* TITLE Geologist DATE November 21, 1989

(This space for Federal or State office use)

APPROVED BY *[Signature]*
CONDITIONS OF APPROVAL, IF ANY:

SUPR. PETROLEUM ENGINEER
Oil & Gas Cons. Comm.

DATE 12/5/89

REC'D NOV 21 1989

H&R Well Services, Inc.
0902 Rd 4
Wiggins, Colorado
80654
303-432-5285 or 654-1600 (metro)

RECEIVED

NOV 22 1989

November 18, 1989

Mr. Mike Cruson - *Consultant*
Berry Energy

COLO. OIL & GAS CONS. COMM.

Re: West Fork #1
NW NW Sec 19-38-55W
Washington County, Colo

Mr. Cruson,

We performed the following work on the above lease.
Please attach this letter to a Form 4 for the Colorado Oil and Gas Commission, as the cement verification. I was contacted by Mr. Ed Dimattio with the Commission on November 17th. He indicated that since I was not a designated agent, I could not file a Form 4 for your company. I had done this on October 21, per our verbal agreement. It is therefore necessary for you to refile the Form 4.

Dumped sand to cover the perforations.
Dumped 5 sacks of cement, tagged sand at 4700 with bailer.
Loaded the hole, and cut casing at 1,600'.
Set 25 sacks of cement 1/2 in and 1/2 out of surface at 60'.
Set 5 sacks at surface.
Cut the wellhead off 4' down, and welded a plate.
Backfilled the hole, and dug the deadmen.
The West Fork Unit is still producing, so the production battery was not dismantled.

Sincerely,



Dave Rebol
H&R Well Services, Inc.

CC: Colo Oil and Gas, attn Ed Dimattio