



00229895

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADORECEIVED
OCT 27 1964OIL & GAS
CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete

☐

Report of Remedial Work

☐

Notice of Intention to Change Plans

☐

Report of Recompleation

☐

Notice of Intention to Abandon Well

☒

Other

☐

(Check appropriate space)

LEASE NAME State of Colorado "B" WELL NO. 9
FIELD Big Beaver WILDCAT _____ COUNTY Washington
LOCATION NE NW Section 16 Township 3S Range 56W Meridian 6
(Quarter Quarter)
670 feet from N Section Line and 1845 feet from W Section Line
N or S E or W

(DETAILS OF WORK)

The well was drilled to 4988.5' total depth in June, 1962. 8-5/8" 24# surface casing set at 128' RDB x cemented with 100 sacks of cement. 5 1/2" 14# J-55 casing was set at 4969' RDB and cemented with 150 sacks of cement. Perforations are at 4970-4974' (muddy J1). The well is no longer capable of producing commercial oil. It was shut in in October 1963 and was producing 5 BOPD and 72 BWPD at the time. We will cut off the 5 1/2" casing as deep as possible and pull.
Plugs as follow:

16 sack sand plug from 4988' to 4874' (to perfs)
5 sack cement plug above perfs
Mud to surface casing shoe
10 sack cement plug from 128'-98' at bottom of surface casing
Mud to top of surface casing
5 sack cement plug at top of surface casing
Weld a plate to top of surface casing

DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

OCT 29 1964

Date

Director

Company Pan American Petroleum Corp. Date Oct. 13, 1964Address P. O. Box 1031, Kimball, Neb. Phone No. BE 5-4603By P. R. Kiff
(Signature)Title Area Foreman