


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

00229894

PLUGGING RECORD

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Pan American Petroleum Corporation Field Big Beaver Wilcat
 Lease Name State of Colorado "B" Well No. 9 County Washington
 Location NE NW Section 16 Township 3S Range 56W Meridian 6
 (Quarter Quarter)
670 feet from N Section line and 1845 feet from W Section Line
 N or S E or W

TOTAL DEPTH 4988.5 RDBDATE OF PLUGGING Nov. 13, 1964 ✓

DETAILS OF WORK

(Measurements from RDB)

Casing left in hole:

1018' 5½" 14#, 4969' to 3951'

117' 8-5/8" 24#, 128' to 11'

Casing pulled: 3945' of 5½" 14#

Plugged as follows:

114 gallons sand, 4988' to 4874'

5 sacks cement, 4874' to 4834'

Mud, 4834' to 128'

10 sacks cement, 128' to 97'

Mud, 97' to 17'

5 sacks cement, 17' to base cellar

Surface casing cut off below plow depth and cap welded to top.

| | |
|------|---|
| | |
| DVR | |
| WRS | |
| HHM | |
| JAM | |
| FJP | ✓ |
| JJD | ✓ |
| FILE | |

Ex
Oil
Prod.

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date DEC 28 1964

Director

Company Pan American Pet. Corp. Date 12-21-64Address P.O. Box 1031, Kimball, Nebr. Phone No. 235-4603By A. A. Wilson Title Area Supt.
(Signature)