




OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



OIL & GAS
CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME State of Colorado "B" WELL NO. 4
 FIELD Big Beaver WILDCAT _____ COUNTY Washington
 LOCATION C NW NE Section 16 Township 3S Range 56W Meridian 6E
 (Quarter Quarter)
600 feet from S Section Line and 1980 feet from W Section Line
 N or S E or W

(DETAILS OF WORK)

This well produced 100% water prior to being temporarily abandoned in June, 1958. Following is the proposed procedure to be followed in abandoning this well.

1. Place 15 sack cement plug across "J" Sand perforations.
2. Pull recoverable amount of 5-1/2" casing.
3. Place 15 sack cement plug across surface casing shoe.
4. Cut surface casing off below plow depth and set 10 sack cement plug in top of surface casing.
5. Clean and level location.

AJJ	
DVR	
WRS	
HMM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Date DEC - 9 1960
 Director [Signature]

Company PAN AMERICAN PETROLEUM CORP Date _____
 Address P. O. Box 1031, Kimball, Neb Phone No. BE5-4603
 By [Signature] Title Area Supt.
 (Signature)

