

Ranger Energy Services, LLC
10350 Richmond Avenue Suite 550
Houston, TX 77042
(713) 935-8900
(713) 935-8901 (FAX)



540004

Unit # C1003

Daily Work Ticket

Day #

Customer Name			Customer AFE #		Date:
Chevron			WBS: UWRWE-A3033- ABN Patricia Albidrez		3/30/2023
Mailing Address		City	State	Zip	County
		CO			Weld County, CO
Field		Lease		Order #	
				SCHMIDT G 19-24	
TVD		MD		Calculated Horizontal Length	
00		00		0	
				Company Rep	
				Patricia Albidrez	

Work Description	
P&A	✓

Sub Code Description	
Cement	✓

Description

Turnkey Rigless Cement Pump Charge
Wireline Charge
Cement Retarder
Water Bobtail Hours
Water
Cement (neat)
Sugar
Miscellaneous Well Site Charge

Description of Work **Start Time** 07:00 AM **Stop Time** 07:00 PM

From	To	Hours	Description	Details	Stage
7:00:08 AM	8:00:08 AM	1	RU/RD cement crew	C1003, MOB to location, started pumping at 12:40 pm, Status: 2-3/8" 4.7# EOT at 6,915' in 4-1/2" 11.6#, pumped 32 bbl. of fresh, 4	
8:00:08 AM	9:00:08 AM	1	RU/RD cement crew	bbl. LCM pill, displaced 25.9 bbl., wait 30 min, established circulation, pumped 117 bbl. total, pumped 5 bbl. fresh, 35 sxs of 15.8# 1.15	
9:00:08 AM	10:00:08 AM	1	RU/RD cement crew	cu.ft./sack Class G cement w/retarder, 7.2 bbl. of slurry, displaced 25.4 bbl. to cover from 6,915' to 6,402', Water details: PH 7.0,	
10:00:08 AM	11:00:08 AM	1	RU/RD cement crew	Chlorides: <150 ppm, Temp: 50F, RD valve, wash out, 4:30 pm RDMO, Non rev: pre trip trucks, prep for jobs, maintain C1002 & 241	

Payroll Section

Employee		Rev Hours	Travel Hours	Non Rev Hours	Total
Tool Pusher	Diaz, Luis M.	9.50	0.00	2.50	12.00
Operator	Winn, Marcus M.	9.50	0.00	0.50	10.00
Derrick	Lopez, Alfonso	3.00	0.00	7.00	10.00
FloorHand	Garcia, Rodolfo F.	3.00	0.00	7.00	10.00
FloorHand	Held, Robert	3.00	0.00	7.00	10.00

No Unreported Incidents Per My
Signature