

Ranger Energy Services, LLC  
10350 Richmond Avenue Suite 550  
Houston, TX 77042  
(713) 935-8900  
(713) 935-8901 (FAX)



536573

Unit # C1003

Daily Work Ticket

Day #

<b>Customer Name</b> Chevron			<b>Customer AFE #</b> WBS: UWRWE-A3026- ABN Patricia Albidrez		<b>Date:</b> 3/23/2023
<b>Mailing Address</b>		<b>City</b>	<b>State</b>	<b>Zip</b>	<b>County</b>
		CO			Weld County, CO
<b>Field</b>		<b>Lease</b>		<b>Well</b>	<b>Order #</b>
				SCHMIDT G 19-22	
<b>TVD</b>		<b>MD</b>		<b>Calculated Horizontal Length</b>	<b>Company Rep</b>
00		00		0	Patricia Albidrez

<b>Work Description</b>	
P&A	✓

<b>Sub Code Description</b>	
Cement	✓

Description of Work    Start Time 05:30 AM    Stop Time 01:00 PM

From	To	Hours	Description	Details	Stage
5:30:45 AM	6:30:45 AM	1	RU/RD cement crew	C1003, MOB to location, started pumping at 9:00 am, Status: 2-3/8" 4.7# EOT at 6,915' in 4-1/2" 11.6#, pumped 32 bbl. of fresh, 4 bbl.	
6:30:45 AM	7:30:45 AM	1	RU/RD cement crew	LCM pill, displaced 25.9 bbl., wait 30 min, established circulation, pumped 110 bbl. total, pumped 5 bbl. fresh, 35 sxs of 15.8# 1.15	
7:30:45 AM	8:30:45 AM	1	RU/RD cement crew	cu.ft./sack Class G cement w/retarder, 7.2 bbl. of slurry, displaced 25.1 bbl. to cover from 6,915' to 6,402', Water details: PH 7.0,	
8:30:45 AM	9:30:45 AM	1	RU/RD cement crew	Chlorides: <150 ppm, Temp: 50F, RD valve, wash out, 12:00 pm RDMO, Non rev: pre trip trucks, prep	

Payroll Section

No Unreported Incidents Per My  
Signature

Ranger Representative

Customer/Agent