



Treatment Report

Customer: Civitas Resources

Job #: JOB00141953

Rep: Kenny
Graham

Rig: Cartel 11

Job Date: Dec 09 @ 21:12

Supervisor: James Ragle

Well: SHELTON 25W-25-13

Time Requested:

Job Type: US Primary

UWI: SHELTON 25W-25-13

Time Arrived: Dec 10 @ 01:12

Casing-
Surface

Surface: SHELTON 25W-25-13

Time Released: Dec 10 @ 10:12

1 Grade	TBD	1 Size (mm, in)	9.625	1 Weight (kg/m, 36 lb/ft)
BHCT (°C, °F)	91	BHST (°C, °F)	108	Collapse Csg Pressure (MPa, psi)
Float Depth (m, ft)	1872	Funnel Vis (sec/L, sec/qt)	TBD	Max Csg Pressure (MPa, psi)
Max Pressure (MPa, psi)	2500	Mud Type	WBM	Plug Size (mm, in)
Plug Type	Rig Supplied	TMD (m, ft)	1915	TVD (m, ft) 1864

Treatment Info:	Tonnes Used:	Tonnes Not Used:	0.00
Preflush:	10m3 Fresh Water & 20m3 MAG Mark	Slurry Temp:	85
Displace:	144.7m3 Fresh Water	Water Temp:	55
Slurry Returns:	30 Plug Bumped:	Bulk Temp:	28
	Yes	Slurry Sample:	Yes
		Water Sample:	Yes
		Slurry Sample:	Yes
		Float Held:	Yes

Time	Pressure MPa	Annular Pressure MPa	Volume Per Stage m3	Total Stage Volume m3	Rate m3/min	Treatment Detail
01:30	0.00	0.00		0.00		Arrive on Location - GET NUMBERS FROM COMPANY MAN, RIG RUNNING CASING/ REQUESTED TIME 3:30AM/ TEST WATER TEMP 55/ CHLORIDES120/ PH8
07:05	0.00	0.00		0.00		Safety Meeting - HOLD MEETING WITH ALL PERSONEL
07:45	75.00	0.00		5.00	3	Fill Lines - DROP BOTTOM PLUG/ FILL LINES WITH FRESH WATER
07:51	3000.00	0.00		0.50		Start Pressure Test - TEST PUMPS AND LINES
07:53	250.00	0.00		25.00	5.5	Pump Preflush - 10BBLS FRESH WATER 20BBLS MAG MARK
08:00	600.00	0.00		195.00	6	Pump Slurry - MIX AND PUMP 764 SKS MAG S 13.3 195 BBLS Y-1.44/ MW-7.01 / 85 #SK
08:39	0.00	0.00		0.00		Stop Pumping
08:41	0.00	0.00		0.00		Drop Plug - DROP TOP PLUG WITNESSED BY COMPANY MAN
08:45	450.00	0.00		100.00	6	Displace - FRESH WATER/ 30BBLS CEMENT TO SURFACE

09:10	0.00	0.00		0.00		Stop Pumping - SHUT DOWN 5 MIN ONCE CEMENT CAME TO SURFACE
09:15	760.00	0.00		34.00	6	Displace - CONTINUE DISPLACEMENT
09:21	820.00	0.00		10.00	3.5	Decrease Rate
09:24	1350.00	0.00		0.00		Bump Plug
09:26	0.00	0.00		0.00		Check Floats - .5 BBLs BACK TO TRUCK/ FLOATS HELD
09:40	0.00	0.00		0.00		Wash Up Truck
10:00	0.00	0.00		0.00		Leave Location



Customer: CIVITAS

Date: 12-10-2022

Ticket: 141953

Location: SHELTON 25W-25-13

Well Name: SHELTON 25W-25-13

Job Type: SURFACE

Magnum Unit #: 1015

