



Treatment Report

Customer: Civitas Resources

Job #: JOB00141955

Rep: Kenny
Graham

Rig: Cartel 11

Job Date: Dec 13 @ 16:12

Supervisor: Vitalijs
Neverdasovs

Well: SHELTON 25W-25-15

Time Requested:

Job Type: US Primary

UWI: SHELTON 25W-25-15

Time Arrived: Dec 11 @ 20:12

Casing-
Surface

Surface: SHELTON 25W-25-15

Time Released: Dec 12 @ 00:12

1 Grade	TBD	1 Size (mm, in)	9.625	1 Weight (kg/m, 36 lb/ft)
BHCT (°C, °F)	91	BHST (°C, °F)	108	Float Depth (m, 1890 ft)
Funnel Vis (sec/L, sec/qt)	TBD	Max Pressure (MPa, psi)	2500	Mud Density (kg/m3, lb/gal) 8.5
Mud Type	water	Plug Size (mm, in)	9 5/8	Plug Type Rig Supplied
TMD (m, ft)	1933	TVD (m, ft)	1860	

Treatment Info:	Tonnes Used:	Tonnes Not Used:	0.00
Preflush:	10m3 Fresh Water & 20m3 MAG Mark	Circulation Time:	0.5
		Slurry Temp:	80 Bulk Sample: Yes
Displace:		Water Temp:	67 Water Sample: Yes
		Bulk Temp:	38 Slurry Sample: Yes
Slurry Returns:	30 Plug Bumped:	Yes Pump Out Lines:	Float Held: Yes

Time	Pressure MPa	Annular Pressure MPa	Volume Per Stage m3	Total Stage Volume m3	Rate m3/min	Treatment Detail
17:00	0.00					Arrive on Location - ARRIVED ON LOCATION. CUSTOMER REQUESTED CREW AT 20:00. RIG IS RINNING CASING
18:00	0.00					TEST WATER : TEMP 67/ CHLORIDES 100/ PH 8
20:44	0.00					Safety Meeting - PRE JOB SAFETY MEETING WITH ALL PERSONEL
21:12	0.00					DROP BOTTOM PLUG
21:16	3300.00		5		3.0	Start Pressure Test - FILL LINES AND PRESSURE TEST
21:18	301.00		5		6.0	PUMP FRESH WATER
21:19	305.00		20		6.0	PUMP DYE
21:22	635.00		195.9		6.0	Pump Slurry - BATCH/ WEIGHT/ PUMP 764 SKS/ 195.9 BBLs 13.3 PPG SLURRY.
22:03	0.00			0.00		Stop Pumping - SHUTDOWN/ DROP TOP PLUG
22:10	672.00		110		6.0	Displace - FRESH WATER DISPLACEMENT.
22:34	0.00					Stop Pumping - GOT CEMENT TO SURFACE. PER CUSTOMER REQUEST SHUT DOWN AND WAIT FOR 5 MINUTES.

22:39	680.00		20		6.0	Displace - CONTINUE DISPLACEMENT
22:42	710.00		16.1		3.5	Slow Rate Pumping - SLOW RATE
22:47	1380.00			146.10		Bump Plug - BUMP PLUG/ 30 BBLS CEMENT TO SURFACE.
22:49	0.00					CHECK FLOATS/ 0.5 BBL BACK
23:00	0.00					Wash Up Truck
23:30	0.00					Rig Out



Customer: CIVITAS

Date: 12/11/2022

Ticket: 141955

Location: SHELTON 25W-25-15

Well Name: SHELTON 25W-25-15

Job Type: SURFACE

Magnum Unit #: 1015

