

FORM

6

Rev  
11/20

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Replug By Other Operator

Document Number:

403211517

Date Received:

04/28/2023

## WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 10656

Contact Name: Jim Jacobsen

Name of Operator: MORNING GUN EXPLORATION LLC

Phone: (720) 326-5262

Address: 1601 ARAPAHOE ST

Fax:

City: DENVER State: CO Zip: 80202

Email: jim.jacobsen@iptwell.com

For "Intent" 24 hour notice required,

Name: Petrie, Erica

Tel: (303) 726-3822

COGCC contact:

Email: erica.petrie@state.co.us

Type of Well Abandonment Report: ☒ Notice of Intent to Abandon ☐ Subsequent Report of Abandonment

API Number 05-123-13455-00

Well Name: HOUSTON

Well Number: 4-X

Location: QtrQtr: SENW Section: 3 Township: 7N Range: 59W Meridian: 6

County: WELD

Federal, Indian or State Lease Number:

Field Name: WILDCAT

Field Number: 99999

## Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.605782

Longitude: -103.965861

GPS Data: GPS Quality Value: 1.5 Type of GPS Quality Value: PDOP Date of Measurement: 04/11/2023

Reason for Abandonment: ☐ Dry ☐ Production Sub-economic ☐ Mechanical Problems☒ Other Option 3 for offset mitigationCasing to be pulled: ☐ Yes ☒ No Estimated Depth:Fish in Hole: ☐ Yes ☒ No If yes, explain details belowWellbore has Uncemented Casing leaks: ☐ Yes ☒ No If yes, explain details below

Details: 4.5" casing already pulled, April 9, 1990, at 5,920'

## Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
D SAND	6692	6724	11/01/1989	SAND PLUG/CEMENT	6434

Total: 1 zone(s)

## Casing History

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top	Status
SURF	12+1/2	8+5/8	Unk	24	0	231	145	231	0	VISU
1ST	7+7/8	4+1/2	Unk	11.6	5920	6824	150	6824	6167	CALC
OPEN HOLE	7+7/8				231	5920				

## Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top. CIBP #2: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
CIBP #3: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top. CIBP #4: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
CIBP #5: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set	65	sks cmt from	5836	ft. to	5636	ft.	Plug Type:	OPEN HOLE	Plug Tagged:	<input type="checkbox"/>
Set	50	sks cmt from	3000	ft. to	2900	ft.	Plug Type:	OPEN HOLE	Plug Tagged:	<input checked="" type="checkbox"/>
Set	65	sks cmt from	1741	ft. to	1541	ft.	Plug Type:	OPEN HOLE	Plug Tagged:	<input checked="" type="checkbox"/>
Set		sks cmt from		ft. to		ft.	Plug Type:		Plug Tagged:	<input type="checkbox"/>
Set		sks cmt from		ft. to		ft.	Plug Type:		Plug Tagged:	<input type="checkbox"/>

Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth

Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth

Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth

(Cast Iron Cement Retainer Depth)

Set 145 sacks half in. half out surface casing from 631 ft. to 181 ft. Plug Tagged: ☒

Set 16 sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☐ No

Set \_\_\_\_\_ sacks in rat hole Set \_\_\_\_\_ sacks in mouse hole

### Additional Plugging Information for Subsequent Report Only

Casing Recovered: \_\_\_\_\_ ft. of \_\_\_\_\_ inch casing

Surface Plug Setting Date: \_\_\_\_\_ Cut and Cap Date: \_\_\_\_\_ Number of Days from Setting Surface Plug to Capping or Sealing the Well: \_\_\_\_\_

\*Wireline Contractor: \_\_\_\_\_

\*Cementing Contractor: \_\_\_\_\_

Type of Cement and Additives Used: \_\_\_\_\_

Flowline/Pipeline has been abandoned per Rule 1105 ☐ Yes ☐ No

Technical Detail/Comments:

This Option 3 offset mitigation is being completed for the wells located on the Castor 7-59 10 Pad (Loc id #471039).

Updated "as drilled" GPS data taken 4/11/2023 has been submitted with this Form 6.

Please find the current and proposed WBD diagrams, surface owner consent and location photos attached.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Kelsi Welch

Title: Compliance Manager Date: 4/28/2023 Email: kelsi.welch@iptwell.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Wolfe, Stephen Date: 5/30/2023

CONDITIONS OF APPROVAL, IF ANY:

Expiration Date: 11/29/2023

COA Type	Description
	<p>Plugging</p> <p>1) Provide electronic Form 42 Notice of MIRU 2 business days ahead of operations and electronic Form 42 Notice of Plugging Operations 48 hours prior to mobilizing for plugging operations.</p> <p>2) Plugs and squeezes will be placed as stated in the Plugging Procedure section of the approved NOIA unless revised by COA or prior approval from COGCC is obtained.</p> <p>3) The wellbore must be static prior to placing cement plugs which are to be a minimum of 100' in length for all but surface plugs. Mechanical isolation requires a 25' cement plug, minimum. For plugs not specified to be tagged, a tag is required if circulation is not maintained while pumping plug and displacing to depth. Tag at tops specified or shallower. Notify COGCC Area Engineer before adding cement to previous plug.</p> <p>4) Place a 50' plug (minimum) at the surface, both inside the inner most casing and in all annular spaces. Surface plugs shall be circulated to surface. Confirm cement to surface in all strings during cut and cap.</p> <p>5) With the Form 6 SRA operator must provide written documentation which positively affirms each COA has been addressed.</p> <p>6) Operator must wait a sufficient time on all plugs to achieve the intended design. If at any time during the plugging there is evidence of previously unreported pressure or fluid migration, contact COGCC Area Engineer before continuing operations.</p> <p>7) Plugging procedure has been modified as follows, Open hole plug(s) set in 1990 that will remain - 6802-6434, Sand with 5 sx cement plug. Include on the Form 6 SRA. Plug #1 - 5836-5636', 65 sx cement open hole plug. Plug #2 - 3000-2900', 50 sx cement open hole plug, WOC and tag. Plug #3 - 1741-1541', 80 sx cement open hole plug, WOC and tag. Plug #4 - 631-181', 145 sx cement open hole plug, WOC and tag. Plug #5 - 50-0', 16 sx of cement per COA #4.</p> <p>8) Submit an updated WBD that corresponds with the approved 6(N) (if needed) prior to filing Form 42 Notifications required in COA #1 above.</p> <p>9) Submit with the Form 6 SRA, if available - the gyro survey planned for in the procedure; any logs not on file with the COGCC.</p>
1 COA	

### **Attachment List**

Att Doc Num	Name
403211517	FORM 6 INTENT SUBMITTED
403211564	WELLBORE DIAGRAM
403211565	WELLBORE DIAGRAM
403387849	LOCATION PHOTO
403387851	SURFACE OWNER CONSENT

Total Attach: 5 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineer	Groundwater=Laramie-Fox Hills, Upper Pierre Deepest water well=360'(1mi, 13 records), 1525'(2mi, 29 records) Log=123-12695 10/9/85 4911 GR, L-FH base 420 UP 810-1495	05/26/2023
OGLA	OGLA review complete and task passed.	05/24/2023
Permit	Submitter supplied as-drilled well location. Submitter attached exhibits. Pass.	05/01/2023
Permit	No other form in process. Production reporting OK. Confirmed productive interval, docnum: 225750. Reviewed WBDs. Missing Surface owner consent and pictures from 4 directions. See option three Offset Well Evaluation and Hydraulic Fracturing Guidance pg 7/8. RTD.	11/01/2022

Total: 4 comment(s)