

**FORM
INSP**Rev
X/20**State of Colorado
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Inspection Date:

05/31/2023

Submitted Date:

06/02/2023

Document Number:

702501396

FIELD INSPECTION FORMLoc ID 312947 Inspector Name: Burchett, Kirby On-Site Inspection ☐ 2A Doc Num: _____**Operator Information:**

OGCC Operator Number: 10372

Name of Operator: X FIELD GAS LLC

Address: PO BOX 1313

City: CRAIG State: CO Zip: 81626

Status Summary:

- ☐ THIS IS A FOLLOW UP INSPECTION
- ☒ FOLLOW UP INSPECTION REQUIRED
- ☐ NO FOLLOW UP INSPECTION REQUIRED

Findings:

16 Number of Comments

12 Number of Corrective Actions

☒ Corrective Action Response Requested**ANY CORRECTIVE ACTION(S) FROM
PREVIOUS INSPECTIONS THAT HAVE NOT
BEEN ADDRESSED ARE STILL APPLICABLE****Contact Information:**

Contact Name	Phone	Email	Comment
Burger, Craig	(970) 319-4194	craig.burger@state.co.us	
Haskins, Jake	(970) 629-2233	haskins2233@gmail.com	
Kellerby, Shaun	(970) 712-1248	shaun.kellerby@state.co.us	

Inspected Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
222979	WELL	SI	05/01/2019	GW	081-06341	JOHNSON 1-28	SI

General Comment:**COGCC Inspection Report Summary**

On Wednesday, 03/31/2023, Inspector Kirby Burchett, conducted a routine field inspection at X Field Gas on the Johnson 1-28 well, Location #312947, in Moffat County, Colorado.

This location is within or in close proximity to a CPW District with Black Bear, High Priority, NSO, Density Habitat Regulations.

Any Corrective Actions from previous Inspections are still applicable.

While there during normal operations the following compliance issues were found:

1. Random debris.
 2. Signs missing required information.
 3. Gas meter calibration overdue.
 4. Insufficient Stormwater BMPs.
 5. Production tank missing required information.
 6. Open end tank valve.
 7. Methanol tank inside insufficient containment
 8. Bradenhead not accessible or visible.
 9. Mechanical Integrity Test overdue.
 10. Location is inaccessible by vehicle quarter mile from location.
 11. Tank berm capacity may be insufficient due to inaccurate depth measurement.
- Refer to attached photographs for Corrective Action.

A follow up on this site inspection will be conducted to ensure all compliance issues have been corrected to comply with COGCC rules.

LocationOverall Good: ☐**Signs/Marker:**

Type	BATTERY		
Comment:	Sign missing required information		
Corrective Action:	The Tank battery sign will be no less than 3 square feet and no more than 6 square feet, and will provide: Name of the Operator; Telephone number at which the Operator can be reached at all times; Telephone number for local emergency services (911 where available); The public road used to access the Tank battery site; Well name(s) and API number(s) associated with the Tank battery and the legal location of the Well(s); and Location, including the quarter/quarter section, of the Tank battery.	Date:	07/31/2023
Type	OTHER		
Comment:	Separator units include attached storage tanks. No form of labeling or markers are present to identify a potential hazard or the contents of the storage tank.		
Corrective Action:		Date:	
Type	TANK LABELS/PLACARDS		
Comment:	Production tank missing required information		
Corrective Action:	All Tanks and Containers will be labeled pursuant to Rule 605. h. (1). All Tanks with a capacity of 10 Barrels or greater will be labeled or posted with the following information: Name of Operator; Operator's emergency contact telephone number; Tank capacity; Tank contents; and NFPA label or equivalent globally harmonized label.	Date:	06/11/2023
Type	WELLHEAD		
Comment:	Wellhead sign missing required information		
Corrective Action:	The Wellhead sign will identify: The Well name; The API number; and Its legal location, including the quarter/quarter section.	Date:	06/11/2023
Type	TANK LABELS/PLACARDS		
Comment:	Methanol tank label peeled off		
Corrective Action:	Containers that are used to store, treat, or otherwise handle a hazardous material and which are required to be marked, placarded, or labeled in accordance with the U.S. Department of Transportation's Hazardous Materials Regulations, will retain the markings, placards, and labels on the Container. Such markings, placards, and labels will be retained on the Container until it is sufficiently cleaned of residue and purged of vapors to remove any potential hazards.	Date:	06/11/2023

Emergency Contact Number:

Comment: 970.629.2233

Corrective Action:

Date: _____

Good Housekeeping:

Type	DEBRIS		
Comment:	Random debris		
Corrective Action:	All trash, rubbish, and other waste material will be properly contained until removed from the Oil and Gas Location. At no time will trash, debris, or rubbish be placed or remain on the ground.	Date:	06/08/2023

Overall Good: ☐**Spills:**

Type	Area	Volume		
------	------	--------	--	--

In Containment: No

Comment:

☐ Multiple Spills and Releases?

Equipment:			corrective date
Type: Ancillary equipment	# 1		
Comment:	Methanol tank on ground inside earth berm. Secondary containment is not sufficiently impervious to contain spilled or released materials.		
Corrective Action:	Install liner material to ensure spill or released materials will be maintained within containment structure.		Date: 07/01/2023
Type: Deadman # & Marked	# 1		
Comment:	2 unmarked anchors		
Corrective Action:	All guy line anchors left buried for future use will be identified by a marker of bright color not less than 4 feet in height and not greater than 1 foot east of the guy line anchor.		Date: 06/16/2023
Type: Bradenhead	# 0		
Comment:	Bradenhead not accessible or visible		
Corrective Action:	Install appropriate fittings to allow Bradenhead visual inspection.		Date: 06/11/2023
Type: Horizontal Heated Separator	# 1		
Comment:			
Corrective Action:			Date:
Type: Gas Meter Run	# 1		
Comment:	Meter hasn't been calibrated since 2017.		
Corrective Action:	Meters will be calibrated annually unless more frequent calibration is required by contractual obligations or by the Director. All calibration reports will be created, maintained, and made available as operation records.		Date: 06/11/2023
Type: Plunger Lift	# 1		
Comment:			
Corrective Action:			Date:
Type: Bird Protectors	# 1		
Comment:			
Corrective Action:			Date:

Tanks and Berms:

Contents	#	Capacity	Type	Tank ID	SE GPS
PRODUCED WATER	1	300 BBLs	STEEL AST		,
Comment:	Open end tank valves				
Corrective Action:	All loadline valves or tank valves that can be used as a loadline will be capped or plugged.				Date: 06/06/2023

Paint

Condition	Adequate	
Other (Content)		
Other (Capacity)		
Other (Type)		

Berms

Type	Capacity	Permeability (Wall)	Permeability (Base)	Maintenance

Earth	Adequate	Walls Sufficent	Base Sufficient	Adequate	
Comment:	Had to walk into location. No tape measure. Tank berm looks to be undersize. Secondary containment needs to contain 150% of the tank volume.				
Corrective Action:					Date:
Venting:					
Yes/No					
Comment:					
Corrective Action:					Date:
Flaring:					
Type					
Comment:					
Corrective Action:					Date:

Inspected FacilitiesFacility ID: 222979 Type: WELL API Number: 081-06341 Status: SI Insp. Status: SI**Idle Well**Purpose: ☒ Shut In ☐ Temporarily Abandoned

Reminder: _____

Comment:

Last Production - April 2019
Last Production Report - June 2020
Reports need to updated as required.

Well is overdue for Mechanical Integrity Test (MIT). MIT requires 10 day notification via Form 42. Well plugging requires an approved Form 6 Intent to Abandon to plug well.

Corrective Action:

Perform successful mechanical integrity test. If a successful MIT cannot be performed within 30 day CA time the well must be plugged within 3 months.

Date: 07/01/2023

Reclamation - Storm Water - Pit**Storm Water:**

Loc Erosion BMPs	BMP Maintenance	Lease Road Erosion BMPs	Lease BMP Maintenance	Chemical BMPs	Chemical BMP Maintenance	Comment

Comment: Stormwater BMPs need implementation and maintenance.
Culvert is washed out 1/4 mile from location preventing access to location in case of emergency.

Corrective Action: Provide proper Stormwater BMPs to control runoff in a manner that minimizes erosion, transport of sediment offsite, and site degradation. Vehicle tracking BMPs to control potential sediment discharges from operational roads, well pads, and other unpaved surfaces.

Date: 06/16/2023

Pits: ☒ NO SURFACE INDICATION OF PIT

Attached Documents

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
403422519	INSPECTION SUBMITTED	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6135221
403422603	INSPECTION SUBMITTED	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6135276
702501405	Inspection Photos	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6133806