



PO Box 329
Ft. Lupton, CO 80621
(303) 654-9202

Well Name				Rig No.		Date		Field Ticket No.			
Aristocrat Angus 44-3C				Axis Rig #718		05/05/23		1395			
State		County		API No.		Customer		Lift Pressure & Pop Off			
CO		Weld		05-123-12762		Civitas - Daniel Nass		Lift:	2,110/388	Pop Off:	1,500/250
Pump		Bulk		Job Type		Last Tckt?		Empl. No.		Employee Name	
2905		2750		Plug/Surface		Yes				Kirk Kallhoff	
Job Supervisor:						Jose Martinez		TBG Dpth:	2,150'/520'	Open Hle:	9"
Edgar Diaz								CSG/ANRL:	33.4 / 8	TBG Vol:	8.3 / 2
Remarks:								Well Information			
G Cement - 135 sks Sugar - 50 lbs								Description		Depth	
								Job #1 Casing Cut		2,200'	
								Job #1 CICR		2,150'	
								Job #1 TOC Calculated		1,900'	
								Job #2 EOT		520'	
Customer Signature:								Job #2 TOC		Surface	
Time		Injection		Pressure		Cement Slurry		Remarks			
		RATE		BBLS IN		PSI		WEIGHT		YIELD	
07:30										Arrive on location	
07:45										JSA, Rig up	
09:25										JSA on pump schedule	
09:35		0.5		0.5		2,000		8.33		Test lines and PRV	
09:40		2		5		360		08:40		Break circulation with H2O	
09:45		2		17.4		280		15.8		1.15	
09:55		2.3		4.3		190		08:40		Mix and pump 85 sks G Cement	
09:57										Shutdown, sting out	
09:58		1.5		2.8		60		08:40		Displace with H2O	
10:00										Shutdown, stand by for Rig work	
11:40										JSA on pump schedule	
11:45		2		5		100		08:40		Break circulation with H2O	
11:50		2		8.1		60		15.8		1.15	
11:55										Mix and pump 40 sks G Cement	
12:40		0.5		2		0		15.8		1.15	
12:45										Shutdown	
12:50										Top Off with 10 sks G Cement	
12:55										Shutdown	
13:30										Wash pumps and lines	
										JSA, Rig down	
										Leave location	
										ARISTOCRAT ANGUS 44-3C	
										AFE: 23111	
										COST CODE: 8523.198	
										ROUTING: TREVIN	
										DANIEL NASS	
										05/05/2023	
Unit		Desc		QTY		RATE		TOTAL		UNIT	
		Pump and Bulk 1st 4 hrs		1						DESC	
		G Cement		135 sks						QTY	
		Sugar		50 lbs						RATE	
		Heavy Duty Mile - Pump		28 mi						TOTAL	
		Heavy Duty Mile - Bulk		28 mi							
Sub Total:											
Customer Approval:											