

FORM  
5A

Rev  
09/20

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 892109



DE	ET	OE	ES
----	----	----	----

Document Number:  
403382911

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: <u>8960</u>	4. Contact Name: <u>Elaine Winick</u>
2. Name of Operator: <u>BONANZA CREEK ENERGY OPERATING COMPANY</u>	Phone: <u>(303) 294-7806</u>
3. Address: <u>410 17TH STREET SUITE #1400</u>	Fax: _____
City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202</u>	Email: <u>ewinick@civiresources.com</u>

5. API Number <u>05-123-51725-00</u>	6. County: <u>WELD</u>
7. Well Name: <u>State Antelope</u>	Well Number: <u>41-11-3HN</u>
8. Location: QtrQtr: <u>SWNW</u> Section: <u>2</u> Township: <u>5N</u> Range: <u>62W</u> Meridian: <u>6</u>	
9. Field Name: <u>WATTENBERG</u> Field Code: <u>90750</u>	

## Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: HYDRAULIC FRACTURING

Treatment Date: 04/08/2023 End Date: 04/16/2023 Date this Formation was Completed: 06/02/2023

Perforations Top: 6741 Bottom: 11804 No. Holes: 1188 Hole size: 36/100 Open Hole:

Describe the Formation Treatment, including the following: type of fluid used (gel, slickwater, etc.), type and concentration of acid used (HCl, HF, etc.), types and amounts of proppant(s) used, depth details of multiple zones, and method used to determine flowback volume.

Frac'd Niobrara with 27 stage plug and perf:  
8305602 total pounds proppant pumped: 4293717 pounds 40/70 mesh; 4011885 pounds 100 mesh;  
288379 total bbls fluid pumped: 281436 bbls gelled fluid; 6598 bbls fresh water and 345 bbls 15% HCl Acid.

This formation is commingled with another formation:  Yes  No

Total fluid used in treatment (bbl): 288379 Max pressure during treatment (psi): 8504

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.30

Type of gas used in treatment: Min frac gradient (psi/ft): 0.89

Total acid used in treatment (bbl): 345 Number of staged intervals: 27

Recycled or Reused Fluids used in treatment (bbl): 0 Flowback volume recovered (bbl): 0

Fresh water used in treatment (bbl): 6598 Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 8305602

**Fracture stimulations must be reported on FracFocus.org**

### Test Information:

06/17/2023 Hours: 24 Bbl oil: 253 Mcf Gas: 155 Bbl H2O: 509

Calculated 24 hour rate: Bbl oil: 253 Mcf Gas: 155 Bbl H2O: 509 GOR: 613

Test Method: flowing Casing PSI: 269 Tubing PSI: 665 Choke Size: 18/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1310 API Gravity Oil: 39

Tubing Size: 2 + 3/8 Tubing Setting Depth: 6385 Tbg setting date: 05/15/2023 Packer Depth: 6383

Reason for Non-Production:

Date formation Abandoned: Squeeze:  Yes  No If yes, number of sacks cmt

\*\* Bridge Plug Depth: \*\* Sacks cement on top: \*\* Wireline and Cement Job Summary must be attached.

Comment:

TPZ 659 FNL & 200 FWL

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Elaine Winick

Title: Completions Tech Date: Email ewinick@civiresources.com

## Attachment List

**Att Doc Num** **Name**

403443011 WELLBORE DIAGRAM

Total Attach: 1 Files

**General Comments**

**User Group**

**Comment**

**Comment Date**

Stamp Upon  
Approval

Total: 0 comment(s)