

McClement #1 Existing WBD		
DESCRIPTION	DEPTH	WELLBORE



WELL:	McClement #1		
LOCATION:	SENE	2	9N
	660 FNL	660FWL	59W
		(Planned)	
	40.781724°N, -103.938579°E		
FORMATION:	JSND	11/10/1957	
API #:	05-123-05728		
Field:	Wildcat		
CURRENT STATUS:	DA		
	Spud: 10/31/1957		
	Plugged: 11/10/1957		

Casing and Tubular Data						
Type	Size	Weight	Top	Bottom	Hole Size	
Surface	8-5/8"	22.0 ppf	0	249'	12-1/4"	
Open-Hole			249'	6909'	7-7/8"	*Assumed

Elevation Data		
GL	4982	feet
KB	<u>4989</u>	feet
Difference	7	feet

Formation Tops Data									
---------------------	--	--	--	--	--	--	--	--	--

<u>Formation</u>	<u>Depth</u>	
Base of Fox Hills	503'	MD
Base of Upper Pierre	1521'	MD
Sussex	4083	MD
Niobrara	5980'	MD
D Sand	6734'	MD
J Sand	6838'	MD